

Final

Site Investigation Report
Fill Area West of Range 19, Parcel 233(7)

Fort McClellan
Calhoun County, Alabama

Prepared for:

U.S. Army Corps of Engineers, Mobile District
109 St. Joseph Street
Mobile, Alabama 36602

Prepared by:

Shaw Environmental, Inc.
312 Directors Drive
Knoxville, Tennessee 37923

Task Order CK09
Contract No. DACA21-96-D-0018
Shaw Project No. 796886

July 2005

Revision 0

Table of Contents

	Page
List of Appendices	iii
List of Tables	iv
List of Figures	iv
Executive Summary	ES-1
1.0 Introduction	1-1
1.1 Project Description	1-1
1.2 Purpose and Objectives	1-2
1.3 Site Description and History	1-3
2.0 Previous Investigations	2-1
3.0 Current Site Investigation Activities	3-1
3.1 UXO Avoidance	3-1
3.2 Fill Area Definition Activities	3-1
3.2.1 Geophysical Survey	3-1
3.2.2 Trenching	3-2
3.3 Environmental Sampling	3-2
3.3.1 Surface and Depositional Soil Sampling	3-2
3.3.2 Subsurface Soil Sampling	3-3
3.3.3 Monitoring Well Installation	3-3
3.3.4 Groundwater Sampling	3-5
3.3.5 Water Level Measurements	3-5
3.3.6 Monitoring Well Abandonment	3-6
3.4 Surveying of Sample Locations	3-6
3.5 Analytical Program	3-6
3.6 Sample Preservation, Packaging, and Shipping	3-7
3.7 Investigation-Derived Waste Management and Disposal	3-7
3.8 Variances/Nonconformances	3-7
3.9 Data Quality	3-8
4.0 Site Characterization	4-1
4.1 Geophysical Survey Results	4-1
4.2 Trenching Results	4-1
4.3 Wetland Determination	4-1
4.4 Regional and Site Geology	4-2

Table of Contents (Continued)

	Page
4.4.1 Regional Geology	4-2
4.4.2 Site Geology	4-6
4.5 Site Hydrology	4-7
4.5.1 Surface Hydrology	4-7
4.5.2 Hydrogeology	4-7
5.0 Summary of Analytical Results	5-1
5.1 Surface and Depositional Soil Analytical Results	5-1
5.2 Subsurface Soil Analytical Results	5-3
5.3 Groundwater Analytical Results	5-4
5.4 Statistical and Geochemical Evaluation of Site Metals Data	5-5
5.5 Additional Chromium and Nickel Groundwater Data Evaluation	5-5
6.0 Summary, Conclusions, and Recommendations	6-1
7.0 References	7-1

Attachment 1 – List of Abbreviations and Acronyms

List of Appendices

Appendix A – Geophysical Survey Report

Appendix B – Trench Logs

Appendix C – Sample Collection Logs and Analysis Request/Chain-of-Custody Records

Appendix D – Boring Logs, Well Construction Logs, and Well Abandonment Forms

Appendix E – Well Development Logs

Appendix F – Survey Data

Appendix G – Variance Reports

Appendix H – Summary of Validated Analytical Data

Appendix I – Data Validation Summary Report

Appendix J – Statistical and Geochemical Evaluation of Site Metals Data

List of Tables

Table	Title	Follows Page
3-1	Sampling Locations and Rationale	3-2
3-2	Soil Sample Designations and Analytical Parameters	3-2
3-3	Monitoring Well Construction Summary	3-4
3-4	Groundwater Sample Designations and Analytical Parameters	3-5
3-5	Groundwater Field Parameters	3-5
3-6	Groundwater Elevations	3-6
3-7	Variances to the Site-Specific Field Sampling Plan	3-7
5-1	Surface and Depositional Soil Analytical Results	5-1
5-2	Subsurface Soil Analytical Results	5-1
5-3	Groundwater Analytical Results	5-1
5-4	Chromium and Nickel Groundwater Analytical Results in Nearby Wells	5-1

List of Figures

Figure	Title	Follows Page
1-1	Site Location Map	1-3
1-2	Site Map	1-3
3-1	Sample Location Map	3-1
4-1	Geophysical Interpretation Map	4-1
4-2	Site Geologic Map	4-6
4-3	Groundwater Elevation Map	4-8

Executive Summary

In accordance with Contract Number DACA21-96-D-0018, Task Order CK09, Shaw Environmental, Inc. (Shaw) completed a site investigation (SI) at the Fill Area West of Range 19, Parcel 233(7), at Fort McClellan (FTMC) in Calhoun County, Alabama. The SI was conducted to determine whether chemical constituents are present at the site as a result of historical mission-related Army activities. The SI consisted of the collection and analysis of six surface soil samples, one depositional soil sample, six subsurface soil samples, and one groundwater sample. Four monitoring wells were installed at the site to facilitate groundwater sample collection and to provide site-specific geological and hydrogeological characterization information. However, only one well produced sufficient groundwater for sampling during the investigation. In addition, a geophysical survey and subsequent trenching were performed on the fill area. An assessment of potential wetlands was also conducted at the fill area.

The geophysical survey identified one area of high conductivity readings. However, exploratory trenching did not indicate the presence of fill material below the ground surface. Additionally, the wetlands study determined that wetlands do not exist on or within 200 feet of Parcel 233(7).

Chemical analysis of samples collected at the site indicates that metals, volatile organic compounds (VOC), semivolatile organic compounds (SVOC), and pesticides were detected in site media. To evaluate whether the detected constituents pose an unacceptable risk to human health or the environment, the analytical results were compared to human health site-specific screening levels (SSSL), ecological screening values (ESV), and background screening values for FTMC. In addition, site metals data were evaluated using statistical and geochemical methods to determine if the metals detected in site media were naturally occurring.

Three metals in soil (barium, iron, and manganese) and two metals in groundwater (chromium and nickel) were detected at concentrations exceeding SSSLs and background (where available) and, thus, were selected as chemicals of potential concern (COPC). The statistical and geochemical evaluations determined that these metals were naturally occurring except for chromium and nickel in groundwater. To address the presence of chromium and nickel in groundwater, groundwater data were evaluated from four additional wells that surround the site. The data from the surrounding wells indicated that chromium was not detected in any of the wells and nickel was detected in only one upgradient well (800 feet away) at a level below the SSSL. Therefore, the chromium and nickel detected in groundwater at Parcel 233(7) appear to

1 be isolated occurrences, and are not believed to pose an unacceptable threat to human health. In
2 addition, the pesticide aldrin was identified as a COPC in groundwater because it was detected at
3 an estimated concentration exceeding its SSSL. A streamlined risk assessment (SRA) was
4 completed as a part of an engineering evaluation/cost analysis (EE/CA) for Parcel 233(7). The
5 SRA concluded that the risk associated with aldrin in groundwater was within acceptable limits.

6
7 Four metals (barium, beryllium, cobalt, and manganese) were detected in surface soil at
8 concentrations exceeding ESVs and background and, thus, were selected as constituents of
9 potential ecological concern (COPEC). However, the statistical and geochemical evaluation
10 determined that these metals were all naturally occurring. The VOC acetone was also identified
11 as a COPEC because it minimally exceeded its ESV in one surface soil sample. Based on the
12 relatively small amount by which the acetone result exceeded the ESV, coupled with the
13 destruction of a significant portion of the terrestrial habitat at the site resulting from construction
14 of the Eastern Bypass Highway, it is concluded that acetone does not pose an unacceptable threat
15 to ecological receptors at this site. This conclusion is consistent with the findings of a screening-
16 level ecological risk assessment completed as part of the EE/CA.

17
18 Based on the results of the SI, including confirmation that fill material is not present, potential
19 historical activities at the Fill Area West of Range 19, Parcel 223(7) have not adversely impacted
20 the environment. The metals and chemical compounds detected in site media do not pose an
21 unacceptable risk to human health or the environment. Therefore, Shaw recommends "No
22 Further Action" and unrestricted land reuse with regard to CERCLA-related hazardous
23 substances at the Fill Area West of Range 19, Parcel 233(7).

1.0 Introduction

The U.S. Army has selected Fort McClellan (FTMC) located in Calhoun County, Alabama, for closure by the Base Realignment and Closure (BRAC) Commission under Public Laws 100-526 and 101-510. The 1990 Base Closure Act, Public Law 101-510, established the process by which U.S. Department of Defense (DOD) installations would be closed or realigned. The BRAC Environmental Restoration Program requires investigation and cleanup of federal properties prior to transfer to the public domain. The U.S. Army is conducting environmental studies of the impact of suspected contaminants at parcels at FTMC under the management of the U.S. Army Corps of Engineers (USACE), Mobile District. The USACE contracted Shaw Environmental, Inc. (Shaw) (formerly IT Corporation [IT]) to perform the site investigation (SI) at the Fill Area West of Range 19, Parcel 233(7), under Contract Number DACA21-96-D-0018, Task Order CK09.

This SI report presents specific information and results compiled from the SI conducted at the Fill Area West of Range 19, Parcel 233(7), including field sampling and analysis, monitoring well installation, well abandonment, fill area definition activities (geophysical surveying and trenching), and wetlands assessment. Furthermore, this SI report is a consolidation of data previously presented in multiple documents associated with Parcel 233(7). Decisions regarding this site made at BRAC Cleanup Team (BCT) meetings are an integral component to the conclusions and recommendations presented herein.

1.1 Project Description

The Fill Area West of Range 19 was identified as an area to be investigated prior to property transfer. The site was classified as a Category 7 parcel in the *Final Environmental Baseline Survey, Fort McClellan, Alabama* (Environmental Science and Engineering, Inc. [ESE], 1998). Category 7 parcels are areas that have not been evaluated and/or that require further evaluation.

A site-specific work plan, comprised of a field sampling plan (SFSP) and a safety and health plan, was finalized in December 1998 (IT, 1998a). The work plan was prepared to provide technical guidance for SI field activities at the Fill Area West of Range 19, Parcel 233(7). The site-specific work plan was used as an attachment to the installation-wide work plan (IT, 1998b) and the installation-wide sampling and analysis plan (SAP) (IT, 1998c). The SAP includes the installation-wide safety and health plan and quality assurance plan.

1 SI field activities included the collection and analysis of six surface soil samples, one
2 depositional soil sample, six subsurface soil samples, and one groundwater sample. Four
3 groundwater monitoring wells were also installed at the site. However, only one well produced
4 sufficient groundwater for sampling. The SI was conducted to determine whether potential site-
5 specific chemicals are present at concentrations that pose an unacceptable risk to human health
6 or the environment.

7
8 The Site Investigation and Fill Area Definition Report documented the initial investigative
9 activities conducted at Parcel 233(7) in 1998 (IT, 2002a). This was followed by an Engineering
10 Evaluation/Cost Analysis (EE/CA) that summarized the site characterization and provided a
11 streamlined risk assessment (SRA) for human health and a screening-level ecological risk
12 assessment (SLERA) in accordance with CERCLA criteria (IT, 2002b).

13
14 The streamlined (limited or qualitative) risk assessment described in EPA guidance for landfills
15 is not identical to the SRA method using site-specific screening levels (SSSL) generally
16 performed for FTMC sites. However, the SRA method lends itself very well to the types of risk
17 assessments prescribed in the landfill guidance. The SRA performed as part of the EE/CA
18 concluded that exposure to soil and groundwater at Parcel 233(7) does not pose a threat to human
19 health (IT, 2002b).

20
21 Additionally, the EE/CA presented the results of the SLERA, which evaluated surface soil at
22 Parcel 233(7). The SLERA indicated that the low levels of constituents of potential ecological
23 concern (COPEC) exceeding ecological screening values (ESV) in surface soil would not present
24 significant risks to the ecosystems at the site. This conclusion was primarily based on the
25 inherent conservatism of the evaluation, the absence of aquatic habitat, and the destruction of the
26 terrestrial habitat by the Eastern Bypass Corridor.

27 28 **1.2 Purpose and Objectives**

29 The SI program was designed to collect data from site media and provide a level of defensible
30 data and information in sufficient detail to determine whether chemical constituents are present
31 at the Fill Area West of Range 19, Parcel 233(7), at concentrations that pose an unacceptable risk
32 to human health or the environment. The SI analytical results were compared to residential
33 SSSLs, ESVs, and background screening values for metals and polynuclear aromatic
34 hydrocarbons (PAH). The SSSLs, ESVs, and PAH background screening values are presented in
35 the *Final Human Health and Ecological Screening Values and PAH Background Summary*

1 *Report* (IT, 2000). Background metals screening values are presented in the *Final Background*
2 *Metals Survey Report, Fort McClellan, Alabama* (Science Applications International
3 Corporation [SAIC], 1998). In addition, site metals data were further evaluated using statistical
4 and geochemical methods to determine if the metals were site related.

5
6 Based on the conclusions presented in this SI report, the BCT will select one of the following
7 courses of action for the site: no further action, additional work, or land use restrictions.


8 9 **1.3 Site Description and History**

10 The Fill Area West of Range 19, Parcel 233(7), is located in the west-central portion of the
11 FTMC Main Post (Figure 1-1). Parcel 233(7) is an elliptical 1.3-acre area measuring
12 approximately 350 feet long by 150 feet wide (Figure 1-2). Iron Mountain Road and Remount
13 Creek are located approximately 500 feet east of the site. Troop Road is located along the
14 northern and eastern boundary of the parcel and provides access to the site from Iron Mountain
15 Road. Parcel 233(7) ranges in elevation from approximately 820 to 845 feet above mean sea
16 level (amsl) and gently slopes to the north toward a tributary to Remount Creek located along the
17 northern boundary of the site.

18
19 Parcel 233(7) was identified as a small “fill area” on a 1949 aerial photograph composite in the
20 Environmental Photographic Interpretation Center report (ESE, 1998). Information was not
21 available regarding the type of material placed at this location.

22
23 The *Fort McClellan Archive Search Report, Conclusions and Recommendations, Revision 1*
24 (USACE, 2001a) identified the area near Parcel 233(7) as the former Combat Range No. 2. The
25 Combat Range No. 2 was built during the inter-war period; however, the initial use of this range
26 is unknown. During World War II, the Combat Range No. 2 area was divided into a rocket
27 range, a hand grenade court, and two rifle/grenade ranges. These ranges were closed or
28 abandoned before 1958. According to the archive search report, 2.36-inch rockets (bazookas)
29 were found on the Rocket Range near Area 17 during a site visit. Additionally, the report states
30 that 3.5-inch rockets may have been used on this range. The Fill Area West of Range 19, Parcel
31 233(7), falls within the “Possible Explosive Ordnance Impact Area” shown on Plate 10 of the
32 *Archive Search Report* (USACE, 2001a).

33
34 Operational dates for the Fill Area West of Range 19 could not be determined from the review of
35 available reports. Information on the type of material stored or disposed of at the site is also




LEGEND

- UNIMPROVED ROADS
- PAVED ROADS
- BUILDING
- FORMER BUILDING
- PARCEL BOUNDARY
- SURFACE DRAINAGE / CREEK
W/ FLOW DIRECTION
- MANMADE SURFACE DRAINAGE FEATURE
W/ FLOW DIRECTION
- UTILITY POLE

FIGURE 1-1
SITE LOCATION MAP
FILL AREA WEST OF RANGE 19
PARCEL 233(7)

U. S. ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
FORT McCLELLAN
CALHOUN COUNTY, ALABAMA
Contract No. DACA21-96-D-0018

dbomar
c:\cadd\design\796886es.185
9/16/2004 9:14:42 AM
STARTING DATE: 11/25/03
DRAWN BY: D. BOMAR
DATE LAST REV.:
DRAWN BY:
DRAFT, CHCK, BY:
ENGR, CHCK, BY: S. MORAN
INITIATOR: J. REMO
PROJ. MGR: J. YACOB
DWG. NO.: ... \796886es.185
PROJ. NO.: 796886



LEGEND

- UNIMPROVED ROADS
- PAVED ROADS
- BUILDING
- FORMER BUILDING
- TOPOGRAPHIC CONTOUR (CONTOUR INTERVAL - 5 FOOT)
- PARCEL BOUNDARY
- SURFACE DRAINAGE / CREEK W/FLOW DIRECTION
- MANMADE SURFACE DRAINAGE FEATURE W/FLOW DIRECTION
- UTILITY POLE
- EASTERN BYPASS CORRIDOR

FIGURE 1-2

SITE MAP

FILL AREA WEST OF RANGE 19

PARCEL 233(7)

U. S. ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
FORT McCLELLAN
CALHOUN COUNTY, ALABAMA
Contract No. DACA21-96-D-0018

Shaw Shaw Environmental, Inc.

1 unavailable. Rocks, metal debris, dirt mounds, and partially exposed crushed drums were
2 observed by Shaw during a site visit. The drums were subsequently removed by another
3 contractor as part of Anniston Eastern Bypass construction activities.

4
5 Parcel 233(7) and the surrounding area were completely cleared during the summer of 2001 for
6 the Anniston Eastern Bypass Highway. Figure 1-2 shows the bypass corridor.

2.0 Previous Investigations

Prior to the SI conducted by Shaw and the Eastern Bypass clearing activities, an environmental baseline survey (EBS) was conducted by ESE to document the environmental condition of all FTMC property (ESE, 1998). The objective of the study was to identify sites that, based on available information, have no history of contamination and comply with DOD guidance for fast-track cleanup at closing installations. The EBS also provides a baseline picture of FTMC properties by identifying and categorizing the properties by seven criteria:

1. Areas where no storage, release, or disposal of hazardous substances or petroleum products has occurred (including no migration of these substances from adjacent areas).
2. Areas where only release or disposal of petroleum products has occurred.
3. Areas where release, disposal, and/or migration of hazardous substances has occurred, but at concentrations that do not require a removal or remedial response.
4. Areas where release, disposal, and/or migration of hazardous substances has occurred, and all removal or remedial actions to protect human health and the environment have been taken.
5. Areas where release, disposal, and/or migration of hazardous substances has occurred, and removal or remedial actions are underway, but all required remedial actions have not yet been taken.
6. Areas where release, disposal, and/or migration of hazardous substances has occurred, but required actions have not yet been implemented.
7. Areas that are not evaluated or require additional evaluation.

The EBS was conducted in accordance with protocols of the Community Environmental Response Facilitation Act (CERFA) (Public Law 102-426) and DOD policy regarding contamination assessment. Record searches and reviews were performed on all reasonably available documents from FTMC, the Alabama Department of Environmental Management (ADEM), EPA Region 4, and Calhoun County, as well as a database search of substances regulated under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), petroleum products, and facilities regulated under the Resource Conservation and Recovery Act. Available historical maps and aerial photographs were reviewed to document historical land uses. Personal and telephone interviews of past and present FTMC employees

1 and military personnel were conducted. In addition, visual site inspections were conducted to
2 verify conditions of specific property parcels. Parcel 233(7) was classified as a CERFA
3 Category 7 parcel in the EBS. Category 7 parcels are areas that have not been evaluated or that
4 require additional evaluation.

3.0 Current Site Investigation Activities

This chapter summarizes SI activities conducted by Shaw at the Fill Area West of Range 19, Parcel 233(7), including unexploded ordnance (UXO) avoidance, environmental sampling and analysis, groundwater monitoring well installation activities, well abandonment, and fill area definition activities.

3.1 UXO Avoidance

UXO avoidance was performed at the Fill Area West of Range 19, Parcel 233(7), following methodology outlined in the SAP. Shaw UXO personnel used a low-sensitivity magnetometer to perform a surface sweep of the parcel prior to site access. After the parcel was cleared for access, sample locations were monitored following procedures outlined in the SAP.

3.2 Fill Area Definition Activities


Shaw performed a geophysical survey and exploratory trenching at Parcel 233(7) to determine the presence or absence of subsurface fill material and, if present, characterize and determine the extent of this material. The geophysical survey area and exploratory trench locations are shown on Figure 3-1.

3.2.1 Geophysical Survey

Shaw conducted a grid-based geophysical survey at Parcel 233(7) to determine the presence or absence of subsurface fill material and, if present, the extent of this material. Shaw used the geophysical survey results to aid in the placement of the exploratory trenches. The geophysical survey was conducted over an approximately 2-acre area encompassing nearly all of Parcel 233(7), as shown on Figure 3-1. A detailed discussion of the geophysical investigation, including theory of instruments operation, field procedures, data processing, and interpreted results, is presented in Appendix A.

The survey was conducted using magnetic and electromagnetic (EM) techniques. The survey grid was established to encompass the suspected disposal site. A detailed site map was drawn in the field identifying any surface features within the survey area or near its perimeter that could potentially affect the geophysical data (e.g., surface metal debris, fencing, and monitoring wells).

dbomar
c:\cadd\design\796886es.186
9/20/2004 3:05:56 PM
STARTING DATE: 11/25/03
DRAWN BY: D. BOMAR
DATE LAST REV.:
DRAFT, CHCK, BY:
ENGR, CHCK, BY: S. MORAN
INITIATOR: J. REMO
PROJ. MGR.: J. YACOB
PROJ. NO.: 796886
DWG. NO.: ... \796886es.186




- ### LEGEND
- UNIMPROVED ROADS
 - PAVED ROADS
 - BUILDING
 - FORMER BUILDING
 - TOPOGRAPHIC CONTOUR (CONTOUR INTERVAL - 25 FOOT)
 - PARCEL BOUNDARY
 - GEOPHYSICAL SURVEY BOUNDARY
 - TRENCH EXCAVATION
 - SURFACE DRAINAGE / CREEK W/FLOW DIRECTION
 - MANMADE SURFACE DRAINAGE FEATURE W/FLOW DIRECTION
 - UTILITY POLE
 - MONITORING WELL (DRY) / SURFACE AND SUBSURFACE SOIL LOCATION
 - MONITORING WELL /GROUNDWATER, SURFACE AND SUBSURFACE SAMPLE LOCATION
 - SURFACE AND SUBSURFACE SOIL SAMPLE LOCATION
 - DEPOSITIONAL SOIL SAMPLE LOCATION
 - ADDITIONAL MONITORING WELL LOCATION (SEE TEXT)

FIGURE 3-1
SAMPLE LOCATION MAP
FILL AREA WEST OF RANGE 19
PARCEL 233(7)

U. S. ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
FORT McCLELLAN
CALHOUN COUNTY, ALABAMA
Contract No. DACA21-96-D-0018

Shaw Shaw Environmental, Inc.



1 Preliminary color contour maps of the data were analyzed and compared with the site sketch to
2 differentiate between anomalies caused by surface and subsurface source materials. The
3 geophysical survey results are summarized in Section 4.1.

4 5 **3.2.2 Trenching**

6 Trenching locations were determined in the field by the site manager based on the geophysical
7 survey results. Prior to trenching, trees and brush were removed to allow access to the trenching
8 locations. Trenching activities were performed in Level C personal protective equipment. The
9 trenches at Parcel 233(7) were excavated using a remote-controlled excavator. Soil and fill
10 materials were stockpiled adjacent to the trench to allow field personnel access for inspection.
11 The on-site geologist recorded the soil lithology and fill material observed in the trenches. Upon
12 completion of inspection of the soil and fill materials, the trenches were backfilled with the
13 excavated material and compacted with the excavator. The trench locations are depicted on
14 Figure 3-1 and the results are summarized in Section 4.2. Appendix B contains the trench logs.

15 16 **3.3 Environmental Sampling**

17 The environmental sampling performed during the SI at the Fill Area West of Range 19, Parcel
18 233(7), included the collection of surface and depositional soil samples, subsurface soil samples,
19 and a groundwater sample for chemical analysis. The sample locations were determined by
20 observing site physical characteristics during site reconnaissance and by reviewing historical
21 documents pertaining to activities conducted at the site. The sample locations, media, and
22 rationale are summarized in Table 3-1. Sampling locations are shown on Figure 3-1. Samples
23 were submitted for laboratory analysis of site-related parameters listed in Section 3.5.

24 25 **3.3.1 Surface and Depositional Soil Sampling**

26 Six surface soil samples and one depositional soil sample were collected at the Fill Area West of
27 Range 19, Parcel 233(7), as shown on Figure 3-1. Soil sampling locations and rationale are
28 presented in Table 3-1. Sample designations and analytical parameters are listed in Table 3-2.
29 Sample locations were determined in the field by the on-site geologist based on UXO avoidance
30 activities, sampling rationale, presence of surface structures, and site topography.

31
32 **Sample Collection.** Surface and depositional soil samples were collected from the uppermost
33 foot of soil using a stainless-steel split-spoon or spoon following methodology specified in the
34 SAP. Prior to collecting the samples, surface material (e.g., rocks and vegetation) was removed
35 from the immediate sample area. The soil was then collected with the sampling device and
36 screened with a photoionization detector (PID) in accordance with procedures outlined in the

Table 3-1

**Sampling Locations and Rationale
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama**

Sample Location	Sample Media	Sampling Location Rationale
PPMP-233-GP01	Surface Soil Subsurface Soil	Surface soil and subsurface soil samples were collected in the southern portion of the parcel to determine if potential site-specific chemicals have impacted the environment.
PPMP-233-GP02	Surface Soil Subsurface Soil	Surface and subsurface soil samples were collected along the northern boundary of the parcel to determine if potential site-specific chemicals have impacted the environment.
PPMP-233-GP03	Surface Soil Subsurface Soil	Surface soil and subsurface soil samples were collected in the northern portion of the parcel to determine if potential site-specific chemicals have impacted the environment.
PPMP-233-GP04	Surface Soil Subsurface Soil Groundwater	Surface soil, subsurface soil, and groundwater samples were collected approximately 85 feet northwest of the parcel to determine if potential site-specific chemicals have impacted the environment.
PPMP-233-GP05	Surface Soil Subsurface Soil	Surface soil and subsurface soil samples were collected in the central portion of the parcel to determine if potential site-specific chemicals have impacted the environment.
PPMP-233-GP06	Surface Soil Subsurface Soil	Surface soil and subsurface soil samples were collected approximately 70 feet southwest of the parcel to determine if potential site-specific chemicals have impacted the environment.
PPMP-233-DEP01	Depositional Soil	A depositional soil sample was collected from a manmade culvert along Iron Mountain Road located southeast of the site to determine if potential site-specific chemicals have impacted the environment.

Table 3-2

Soil Sample Designations and Analytical Parameters
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama

Sample Location	Sample Designation	Sample Depth (ft bgs)	QA/QC Samples			Analytical Parameters
			Field Duplicates	Field Splits	MS/MSD	
PPMP-233-GP01	PPMP-233-GP01-SS-KZ0001-REG	0-1	PPMP-233-GP01-SS-KZ0002-FD	PPMP-233-GP01-SS-KZ0003-FS		Metals, VOCs, SVOCs, PCBs, Pesticides, Herbicides
	PPMP-233-GP01-DS-KZ0004-REG	10-12				
PPMP-233-GP02	PPMP-233-GP02-SS-KZ0005-REG	0-1			PPMP-233-GP02-SS-KZ0005-MS PPMP-233-GP02-SS-KZ0005-MSD	Metals, VOCs, SVOCs, PCBs, Pesticides, Herbicides
	PPMP-233-GP02-DS-KZ0006-REG	10-12				
PPMP-233-GP03	PPMP-233-GP03-SS-KZ0007-REG	0-1				Metals, VOCs, SVOCs, PCBs, Pesticides, Herbicides
	PPMP-233-GP03-DS-KZ0008-REG	10-12				
PPMP-233-GP04	PPMP-233-GP04-SS-KZ0009-REG	0-1				Metals, VOCs, SVOCs, PCBs, Pesticides, Herbicides
	PPMP-233-GP04-DS-KZ0010-REG	10-12				
PPMP-233-GP05	PPMP-233-GP05-SS-KZ0011-REG	0-1				Metals, VOCs, SVOCs, PCBs, Pesticides, Herbicides, Explosives ^a
	PPMP-233-GP05-DS-KZ0012-REG	10-12				
PPMP-233-GP06	PPMP-233-GP06-SS-KZ0013-REG	0-1				Metals, VOCs, SVOCs, PCBs, Pesticides, Herbicides
	PPMP-233-GP03-DS-KZ0014-REG	8-10				
PPMP-233-DEP01	PPMP-233-DEP01-DEP-KZ0015-REG	0-1				Metals, VOCs, SVOCs, PCBs, Pesticides, Herbicides

^aSubsurface soil sample only.

FD - Field duplicate.

FS - Field split.

ft bgs - Feet below ground surface.

MS/MSD - Matrix spike/matrix spike duplicate.

PCB - Polychlorinated biphenyl.

QA/QC - Quality assurance/quality control.

REG - Regular field sample.

VOC - Volatile organic compound.

SVOC - Semivolatile organic compound.

1 SAP. The soil fraction for volatile organic compound (VOC) analysis was collected directly
2 from the sample device using three EnCore® samplers. The remaining soil was then transferred
3 to a clean stainless-steel bowl, homogenized, and placed in the appropriate sample containers.
4 The samples were analyzed for the parameters listed in Table 3-2 using methods outlined in
5 Section 3.5. Sample collection logs are included in Appendix C.

6 7 **3.3.2 Subsurface Soil Sampling**

8 Subsurface soil samples were collected from six soil borings at the Fill Area West of Range 19,
9 Parcel 233(7), as shown on Figure 3-1. Subsurface soil sampling locations and rationale are
10 presented in Table 3-1. Subsurface soil sample designations, depths, and analytical parameters
11 are listed in Table 3-2. Soil boring locations were determined in the field by the on-site geologist
12 based on UXO avoidance activities, the sampling rationale, the presence of surface structures,
13 and site topography.

14
15 **Sample Collection.** Subsurface soil samples were collected from soil borings at depths of 8 to
16 12 feet below ground surface (bgs) in the unsaturated zone. The soil borings were advanced and
17 soil samples collected using a stainless-steel split-spoon following procedures specified in the
18 SAP. Sample collection logs are included in Appendix C. The samples were analyzed for the
19 parameters listed in Table 3-2 using methods outlined in Section 3.5.

20
21 Subsurface soil samples were collected continuously to 12 feet bgs or until split-spoon sampler
22 refusal was encountered. Samples were field screened using a PID to measure volatile organic
23 vapors. The soil sample displaying the highest reading was selected and sent to the laboratory
24 for analysis; however, at those locations where PID readings were below background, the
25 deepest soil sample interval above the saturated zone was submitted for analysis. The soil
26 fraction for VOC analysis was collected directly from the sample device using three EnCore
27 samplers. The remaining sample was then transferred to a clean stainless-steel bowl,
28 homogenized, and placed in the appropriate sample containers. Samples submitted for
29 laboratory analysis are summarized in Table 3-2. The on-site geologist constructed a detailed
30 boring log for each soil boring. The boring logs are included in Appendix D. At the completion
31 of soil sampling, boreholes were abandoned with hydrated bentonite pellets following borehole
32 abandonment procedures summarized in the SAP.

33 34 **3.3.3 Monitoring Well Installation**

35 Four permanent monitoring wells were installed at the Fill Area West of Range 19, Parcel
36 233(7), to collect groundwater samples for laboratory analysis. However, only one of the wells

1 (PPMP-233-GP04) produced sufficient groundwater for sampling. The well/groundwater sample
2 locations are shown on Figure 3-1. Table 3-3 summarizes construction details of the monitoring
3 wells installed at the site. The well construction logs are included in Appendix D.

4
5 Shaw contracted Miller Drilling Company to install the wells at locations PPMP-233-GP03
6 through PPMP-223-GP06 using a combination of hollow-stem auger and air-rotary drilling
7 methods, following procedures outlined in the SAP. An air-rotary drill rig was used in situations
8 where hollow-stem auger refusal was encountered prior to reaching groundwater.

9
10 The borehole for each well was advanced with a 4¼-inch inside diameter (ID) hollow-stem auger
11 from ground surface to the first water-bearing zone at the well location. If hollow-stem auger
12 refusal was encountered prior to reaching groundwater or bedrock, air-rotary drilling was used to
13 continue advancement of the borehole. For the first 12 feet, a 2-foot-long, 2-inch ID stainless-
14 steel split-spoon sampler was driven continuously to collect soil for laboratory analysis and for
15 describing lithology. After the first 12 feet, a 2-foot-long, 2-inch ID carbon-steel split-spoon
16 sampler was driven at 5-foot intervals to collect samples for observing and describing lithology.
17 Where split-spoon refusal was encountered, the auger was advanced until the first water-bearing
18 zone was encountered. The on-site geologist logging the auger boreholes at the site continued
19 the detailed lithological log for each borehole from the depth of split-spoon refusal to the bottom
20 of the auger borehole by logging the auger drill cuttings. Air-rotary drill cuttings were described
21 in detail when an air rig was used. The split-spoon samples and drill cuttings were logged to
22 determine lithologic changes and to approximate the depth at which groundwater was
23 encountered during drilling. This information was used to determine the optimal placement of
24 the monitoring well screen interval and to provide site-specific geologic and hydrogeologic
25 information. Soil characteristics were described using the "Burmeister Identification System"
26 described in Hunt (1986) and the Unified Soil Classification System as outlined in American
27 Society for Testing and Materials (ASTM) Method D2488 (ASTM, 2000). The lithological logs
28 are included in Appendix D.

29
30 Upon reaching the target depth in each borehole, a 20- or 30-foot length of 2-inch ID, 0.010-inch
31 continuous slot, Schedule 40 polyvinyl chloride (PVC) screen with a PVC end cap (or
32 approximately 2-foot sump) was placed through the auger to the bottom of the borehole. The
33 screen and end cap (or sump) were attached to a 2-inch ID, flush-threaded Schedule 40 PVC
34 riser. A sand pack consisting of Number 1 filter sand (environmentally safe, clean fine sand,
35 sieve size 20 to 40) was tremied around the well screen to approximately 5 feet above the top of

Table 3-3

**Monitoring Well Construction Summary
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama**

Monitoring Well	Northing	Easting	Ground Elevation (ft amsl)	TOC Elevation (ft amsl)	Well Depth (ft bgs)	Screen Length (ft)	Screen Interval (ft bgs)
PPMP-233-GP03	1165091.23	664302.44	826.00	828.31	78	20	57.7 - 77.7
PPMP-233-GP04	1165184.79	664160.21	827.06	829.54	79	20	57 - 77
PPMP-233-GP05	1164930.11	664258.95	830.68	833.23	69	30	39 - 69
PPMP-233-GP06	1164777.03	664175.11	841.05	843.51	81.1	20	60.8 - 80.8

Permanent residuum wells installed using hollow-stem auger and/or air-rotary drilling.
All wells constructed of 2-inch inside diameter, Schedule 40, polyvinyl chloride.

Horizontal coordinates referenced to the U.S. State Plane Coordinate System, Alabama East Zone, North America Datum of 1983.
Elevations referenced to the North America Vertical Datum of 1988.

amsl - Above mean sea level.

bgs - Below ground surface.

ft - Feet

TOC- Top of casing.

1 the well screen. A bentonite seal, consisting of approximately 3 feet of bentonite pellets, was
2 placed immediately on top of the sand pack and hydrated with potable water. If the bentonite
3 seal was installed below the water table surface, the bentonite pellets were allowed to hydrate in
4 the groundwater. Bentonite seal placement and hydration followed procedures outlined in the
5 SAP. Bentonite-cement grout was tremied into the remaining annular space of the well from the
6 top of the bentonite seal to ground surface. A well cap was placed on the PVC riser. A locking
7 protective steel casing was placed around the top of the PVC well casing and a cement pad was
8 constructed around the wellhead.

9
10 The wells were developed by surging and pumping with a submersible pump in accordance with
11 methodology outlined in the SAP. The submersible pump used for well development was moved
12 in an up-and-down fashion to encourage any residual well installation materials to enter the well.
13 These materials were then pumped out of the well to reestablish natural hydraulic flow
14 conditions. Development continued until the water turbidity was less than 20 nephelometric
15 turbidity units, until the well was repeatedly pumped dry, or for a maximum of 8 hours. The
16 well development logs are included in Appendix E.

17 18 **3.3.4 Groundwater Sampling**

19 A groundwater sample was collected from one of the four monitoring wells (PPMP-233-GP04)
20 installed at the Fill Area West of Range 19, Parcel 233(7). The other three wells did not contain
21 sufficient water for sampling. The groundwater sample location is shown on Figure 3-1 and the
22 sampling rationale is listed in Table 3-1. Groundwater sample designations and analytical
23 parameters are listed in Table 3-4.

24
25 **Sample Collection.** The groundwater sample was collected using a submersible pump
26 equipped with Teflon™ tubing following procedures outlined in the SAP. Groundwater was
27 sampled after purging a minimum of three well volumes and after field parameters (temperature,
28 pH, specific conductivity, oxidation-reduction potential, and turbidity) stabilized. Groundwater
29 field parameters were measured using a calibrated water quality meter, as summarized in Table
30 3-5. Sample collection logs are included in Appendix C. The sample was analyzed for the
31 parameters listed in Table 3-4 using methods outlined in Section 3.5.

32 33 **3.3.5 Water Level Measurements**

34 The depth to groundwater was measured in PPMP-233-GP04 and in nearby wells at adjacent
35 parcels on June 11, 2001, following procedures outlined in the SAP. Depth to groundwater was
36 measured with an electronic water-level meter. The meter probe and cable were cleaned before

Table 3-4

**Groundwater Sample Designations and Analytical Parameters
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama**

Sample Location	Sample Designation	QA/QC Samples	Analytical Parameters
		Field Duplicates	
PPMP-233-GP04	PPMP-233-GP04-GW-KZ3004-REG	PPMP-233-GP04-GW-KZ3002-FD	Metals, VOCs, SVOCs, PCBs, Pesticides, Herbicides

FD- Field duplicate.

PCB - Polychlorinated biphenyl.

QA/QC - Quality assurance/quality control.

SVOC - Semivolatile organic compound.

VOC - Volatile organic compound.

Table 3-5

**Groundwater Field Parameters
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama**

Sample Location	Date	Conductivity (mS/cm)	DO (mg/L)	ORP (mV)	Temperature (°C)	Turbidity (NTU)	pH (SU)
PPMP-233-GP04	14-Jul-00	0.016	NA	165	18.3	9.7	4.43

°C - Degree Celsius.

DO - Dissolved oxygen.

mg/L - Milligrams per liter.

mS/cm - Millisiemen per centimeter.

mV - Millivolt.

NA - Not available due to equipment malfunction.

NTU - Nephelometric turbidity unit.

ORP - Oxidation-reduction potential.

SU - Standard unit.

1 use at each well following decontamination methodology presented in the SAP. Measurements
2 were referenced to the top of the PVC well casing, as summarized in Table 3-6.

3 **3.3.6 Monitoring Well Abandonment**

5 The monitoring wells at Parcel 233(7) were abandoned as part of the Eastern Bypass Corridor
6 clearing activities on or prior to September 13, 2002, as outlined in the SAP. Well abandonment
7 forms are included in Appendix D.

9 **3.4 Surveying of Sample Locations**

10 Sample locations were surveyed using global positioning system and conventional civil survey
11 techniques described in the SAP. Horizontal coordinates were referenced to the U.S. State Plane
12 Coordinate System, Alabama East Zone, North American Datum of 1983. Elevations were
13 referenced to the North American Vertical Datum of 1988. Horizontal coordinates and
14 elevations are included in Appendix F.

16 **3.5 Analytical Program**

17 Samples collected during the SI were analyzed for various chemical and physical parameters
18 based on the potential site-specific chemicals and EPA, ADEM, FTMC, and USACE
19 requirements. The samples were analyzed for the following parameters using EPA SW-846
20 methods, including Update III methods where applicable:

- 21 • Target compound list (TCL) VOCs – EPA Method 8260B
- 22 • TCL semivolatile organic compounds (SVOC) – EPA Method 8270C
- 23 • Target analyte list metals – EPA Method 6010B/7470A/7471A
- 24 • Chlorinated pesticides – EPA Method 8081A
- 25 • Polychlorinated biphenyls (PCB) – EPA Method 8082
- 26 • Organophosphorus pesticides – EPA Method 8141A
- 27 • Chlorinated herbicides – EPA Method 8151A
- 28 • Nitroaromatic/nitramine explosives – EPA Method 8330 (subsurface soil sample
29 location PPMP-233-GP05 only).

Table 3-6

**Groundwater Elevations
Fill Area West of Range 19, Parcel 233(7) and Vicinity
Fort McClellan, Calhoun County, Alabama**

Well Location	Date	Depth to Water (ft BTOC)	Top of Casing Elevation (ft amsl)	Ground Elevation (ft amsl)	Groundwater Elevation (ft amsl)
PPMP-233-GP04	11-Jun-01	41.39	829.54	827.06	788.15
Wells at Adjacent Parcels					
HR-73Q-MW02	11-Jun-01	42.02	850.23	848.22	808.21
HR-73Q-MW03	11-Jun-01	85.41	949.47	947.49	864.06
HR-228Q-MW02	11-Jun-01	42.33	820.86	818.82	778.53
HR-232QX-MW14	11-Jun-01	18.85	822.99	820.97	804.14
HR-232QX-MW15	11-Jun-01	83.24	834.99	832.99	751.75

Elevations referenced to the North American Vertical Datum of 1988 (NAVD88).

amsl - Above mean sea level.

BTOC - Below top of casing.

ft - Feet.

3.6 Sample Preservation, Packaging, and Shipping

Sample preservation, packaging, and shipping followed requirements specified in the SAP. Sample containers, sample volumes, preservatives, and holding times for the analyses required in this SI are listed in the SAP. Sample documentation and chain-of-custody records were completed as specified in the SAP.

Completed analysis request and chain-of-custody records (Appendix C) were included with each shipment of sample coolers to the analytical laboratory. Samples were shipped to Quanterra Environmental Services in Knoxville, Tennessee. Split samples were shipped to the USACE South Atlantic Division Laboratory in Marietta, Georgia.

3.7 Investigation-Derived Waste Management and Disposal

Investigation-derived waste (IDW) was managed and disposed as outlined in the SAP. The IDW generated during the SI at the Fill Area West of Range 19, Parcel 233(7), was segregated as follows:

- Drill cuttings
- Purge water from well development, sampling activities, and decontamination fluids
- Spent well materials and personal protective equipment.

Solid IDW was stored inside the fenced area surrounding Buildings 335 and 336 in lined roll-off bins prior to characterization and final disposal. Solid IDW was characterized using toxicity characteristic leaching procedure analyses. Based on the results, solid IDW generated during the SI was disposed as nonhazardous waste at the Industrial Waste Landfill on the Main Post of FTMC.

Liquid IDW was contained in the 20,000-gallon sump associated with the Building T-338 vehicle washrack. Liquid IDW was characterized by VOC, SVOC, and metals analyses. Based on the analyses, liquid IDW was discharged as nonhazardous waste to the FTMC wastewater treatment plant on the Main Post.

3.8 Variances/Nonconformances

Three variances to the SFSP were recorded during completion of the SI at the Fill Area West of Range 19, Parcel 233(7). The variances are summarized in Table 3-7 and the variance reports are included in Appendix G.

Table 3-7

**Variances to the Site-Specific Field Sampling Plan
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama**

Variance to the SFSP	Justification for Variance	Impact to Site Investigation
Only two of the four proposed exploratory trenches were excavated at the site.	Geophysical survey did not indicate substantial buried metal or subsurface disturbance indicative of waste disposal. Hence, a decision was made to install only two intersecting trenches in an area where the geophysical survey indicated the greatest potential of encountering buried fill materials.	None. Fill material was not observed during trenching operations.
Subsurface soil boring FA-233-SB01 was not installed.	The SFSP proposed PPMP-233-GP05 at approximately the same location as FA-233-SB01 with the same analyses.	None.
Groundwater samples were not collected from monitoring wells PPMP-233-GP03, PPMP-233-GP05, or PPMP-233-GP06.	Groundwater was encountered during drilling activities, but during groundwater sampling activities these wells were dry or did not contain sufficient groundwater for sampling. Several attempts were made to collect a groundwater sample from each well, but all attempts were unsuccessful.	All four groundwater monitoring wells were installed on bedrock. However, only one well (PPMP-233-GP04) produced sufficient water. Because fill material is not present (i.e., a source area of contamination does not exist) and because of the reuse of the parcel (Eastern Bypass), it was determined that bedrock monitoring wells were not required. Therefore, the potential impact to the site investigation is determined to be inconsequential.

SFSP - Site-specific field sampling plan.

1 Nonconformances to the SFSP were not recorded during completion of the SI.

3 **3.9 Data Quality**

4 The field sample analytical data are presented in tabular form in Appendix H. The field samples
5 were collected, documented, handled, analyzed, and reported in a manner consistent with the SI
6 work plan, the FTMC SAP and quality assurance plan, and standard, accepted methods and
7 procedures. Data were reported and evaluated in accordance with Corps of Engineers South
8 Atlantic Savannah Level B criteria (USACE, 2001b) and the stipulated requirements for the
9 generation of definitive data presented in the SAP. Chemical data were reported via hard-copy
10 data packages by the laboratory using Contract Laboratory Program-like forms.

11
12 **Data Validation.** The reported analytical data were validated in accordance with EPA National
13 Functional Guidelines by Level III criteria. The data validation summary report is included in
14 Appendix I. Selected results were rejected or otherwise qualified based on the implementation
15 of accepted data validation procedures and practices. These qualified parameters are highlighted
16 in the report. The validation-assigned qualifiers were added to the ShawView™ database for
17 tracking and reporting. The qualified data were used in the comparisons to the SSSLs and ESVs.
18 Rejected data (assigned an “R” qualifier) were not used in the comparisons to the SSSLs and
19 ESVs. The data presented in this report, except where qualified, meet the principle data quality
20 objective for this SI.

4.0 Site Characterization

This chapter presents the results of the geophysical survey, trenching activities, and wetlands study conducted at the Fill Area West of Range 19, Parcel 233(7), as well as information on regional and site geology, and site hydrology.

4.1 Geophysical Survey Results

A surface geophysical survey was conducted at Parcel 233(7) using magnetic and EM techniques. The objectives of this survey were to determine the presence or absence of subsurface fill and, if present, delineate the extent of this material. The results of the survey did not reveal the presence of substantial buried metal or subsurface disturbance indicative of significant waste disposal. However, one area of anomalously high conductivity readings was noted in the northeast portion of the site. Possible sources for this anomaly include surface disposal or placement of conductive fill, local increase in the volume of fine-grained sands at the surface associated with construction activities, or an abandoned road grade partially covered with soil. Figure 4-1 is a geophysical interpretation map showing the locations of individual surface metal objects, areas of low to moderate concentrations of surface metals, and the high conductivity anomaly. The anomalies shown on Figure 4-1 correspond to those shown in the magnetic and EM data contour maps presented in the geophysical survey report (Appendix A). A detailed discussion of the data interpretation is included in the geophysical survey report.

4.2 Trenching Results


Exploratory trenching was performed within the area of the high conductivity anomaly in an attempt to determine its source. Trench excavations consisted of one 50-foot-long trench (T233-1A) crossed by a 30-foot-long trench (T233-1B). These trenches were excavated to depths of 3 to 6 feet bgs. Trench logs completed during excavation of the trenches do not indicate the presence of fill material below ground surface. The trench locations are shown on Figure 3-1 and the trench logs are presented in Appendix B.

4.3 Wetland Determination

An assessment of wetlands located within an approximate 200-foot perimeter of Parcel 233(7) was performed in December 2002. Potential wetlands were delineated in accordance with the *Corps of Engineers Wetlands Delineation Manual* (USACE, 1987) to determine the extent of federally regulated jurisdictional wetlands and waters of the United States. The USACE-Mobile District approved the wetland determination for a five-year period on April 2, 2003.

9/16/2004 10:16:37 AM
c:\cadd\design\796886es.187
dbomar

DATE LAST REV.:	DRAWN BY: D. BOMAR	STARTING DATE: 11/26/03	DATE LAST REV.:	ENGR., CHCK, BY: S. MORAN	INITIATOR: J. REMO	DWG. NO.: ...796886es.187
					PROJ. MGR.: J. YACOB	PROJ. NO.: 796886



LEGEND


- GEOPHYSICAL SURVEY BOUNDARY
- ▭ PARCEL BOUNDARY
- ▭ LOW CONCENTRATION OF BURIED METAL
- ▭ HIGH CONDUCTIVITY ANOMALY
- ▭ LOW CONCENTRATION OF SURFACE AND/OR PARTIALLY BURIED METAL DEBRIS
- ▭ GRAVEL
- ◆ SURFACE METAL OBJECT
- TRENCH EXCAVATION
- MOUND
- TOPOGRAPHIC CONTOUR (CONTOUR INTERVAL - 25 FOOT)
- SURFACE DRAINAGE / CREEK W/FLOW DIRECTION
- MANMADE SURFACE DRAINAGE FEATURE W/FLOW DIRECTION
- UTILITY POLE
- MONITORING WELL / SURFACE AND SUBSURFACE SOIL SAMPLE LOCATION
- MONITORING WELL / GROUNDWATER SURFACE, AND SUBSURFACE SOIL SAMPLE LOCATION
- SURFACE AND SUBSURFACE SOIL SAMPLE LOCATION
- ▲ DEPOSITIONAL SOIL SAMPLE LOCATION

SCALE

0 100 200 FEET

FIGURE 4-1
GEOPHYSICAL INTERPRETATION MAP
FILL AREA WEST OF RANGE 19
PARCEL 233(7)

U. S. ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
FORT McCLELLAN
CALHOUN COUNTY, ALABAMA
Contract No. DACA21-96-D-0018

 Shaw Environmental, Inc.

1
2 The wetland determination concluded that wetlands or jurisdictional waters of the United States
3 do not exist on or within 200 feet of the parcel (Shaw, 2003a).
4

5 **4.4 Regional and Site Geology**

6

7 **4.4.1 Regional Geology**

8 Calhoun County includes parts of two physiographic provinces, the Piedmont Upland Province
9 and the Valley and Ridge Province. The Piedmont Upland Province occupies the extreme
10 eastern and southeastern portions of the county and is characterized by metamorphosed
11 sedimentary rocks. The generally accepted range in age of these metamorphics is Cambrian to
12 Devonian.
13

14 The majority of Calhoun County, including the Main Post of FTMC, lies within the Appalachian
15 fold-and-thrust structural belt (Valley and Ridge Province), where southeastward-dipping thrust
16 faults with associated minor folding are the predominant structural features. The fold-and-thrust
17 belt consists of Paleozoic sedimentary rocks that have been asymmetrically folded and thrust-
18 faulted, with major structures and faults striking in a northeast-southwest direction.
19

20 Northwestward transport of the Paleozoic rock sequence along the thrust faults has resulted in
21 the imbricate stacking of large slabs of rock referred to as thrust sheets. Within an individual
22 thrust sheet, smaller faults may splay off the larger thrust fault, resulting in imbricate stacking of
23 rock units within an individual thrust sheet (Osborne and Szabo, 1984). Geologic contacts in this
24 region generally strike parallel to the faults, and repetition of lithologic units is common in
25 vertical sequences. Geologic formations within the Valley and Ridge Province portion of
26 Calhoun County have been mapped by Warman and Causey (1962), Osborne and Szabo (1984),
27 and Moser and DeJarnette (1992), and vary in age from Lower Cambrian to Pennsylvanian.
28

29 The basal unit of the sedimentary sequence in Calhoun County is the Cambrian Chilhowee
30 Group. The Chilhowee Group consists of the Cochran, Nichols, Wilson Ridge, and Weisner
31 Formations (Osborne and Szabo, 1984), but in Calhoun County is either undifferentiated or
32 divided into the Cochran and Nichols Formations and an upper, undifferentiated Wilson Ridge
33 and Weisner Formation. The Cochran is composed of poorly sorted arkosic sandstone and
34 conglomerate with interbeds of greenish gray siltstone and mudstone. Massive to laminated
35 greenish gray and black mudstone makes up the Nichols Formation, with thin interbeds of

1 siltstone and very fine-grained sandstone (Osborne et al., 1988). These two formations are
2 mapped only in the eastern part of the county.

3
4 The Wilson Ridge and Weisner Formations are undifferentiated in Calhoun County and consist
5 of both coarse-grained and fine-grained clastics. The coarse-grained facies appears to dominate
6 the unit and consists primarily of coarse-grained, vitreous quartzite and friable, fine- to coarse-
7 grained, orthoquartzitic sandstone, both of which locally contain conglomerate. The fine-grained
8 facies consists of sandy and micaceous shale and silty, micaceous mudstone, which are locally
9 interbedded with the coarse clastic rocks. The abundance of orthoquartzitic sandstone and
10 quartzite suggests that most of the Chilhowee Group bedrock in the vicinity of FTMC belongs to
11 the Weisner Formation (Osborne and Szabo, 1984).

12
13 The Cambrian Shady Dolomite overlies the Weisner Formation northeast, east, and southwest of
14 the Main Post and consists of interlayered bluish gray or pale yellowish gray sandy dolomitic
15 limestone and siliceous dolomite with coarsely crystalline, porous chert (Osborne et al., 1989).
16 A variegated shale and clayey silt have been included within the lower part of the Shady
17 Dolomite (Cloud, 1966). Material similar to this lower shale unit was noted in core holes drilled
18 by the Alabama Geologic Survey on FTMC (Osborne and Szabo, 1984). The character of the
19 Shady Dolomite in the FTMC vicinity and the true assignment of the shale at this stratigraphic
20 interval are still uncertain (Osborne, 1999).

21
22 The Rome Formation overlies the Shady Dolomite and locally occurs to the northwest and
23 southeast of the Main Post, as mapped by Warman and Causey (1962) and Osborne and Szabo
24 (1984), and immediately to the west of Reilly Airfield (Osborne and Szabo, 1984). The Rome
25 Formation consists of variegated, thinly interbedded grayish red-purple mudstone, shale,
26 siltstone, and greenish red and light gray sandstone, with locally occurring limestone and
27 dolomite. Weaver Cave, located approximately 1 mile west of the northwest boundary of the
28 Main Post, is situated in gray dolomite and limestone mapped as the Rome Formation (Osborne
29 et al., 1997). The Conasauga Formation overlies the Rome Formation and occurs along
30 anticlinal axes in the northeastern portion of Pelham Range (Warman and Causey, 1962;
31 Osborne and Szabo, 1984) and the northern portion of the Main Post (Osborne et al., 1997). The
32 Conasauga Formation is composed of dark gray, finely to coarsely crystalline, medium- to thick-
33 bedded dolomite with minor shale and chert (Osborne et al., 1989).

1 Overlying the Conasauga Formation is the Knox Group, which is composed of the Copper Ridge
2 and Chepultepec dolomites of Cambro-Ordovician age. The Knox Group is undifferentiated in
3 Calhoun County and consists of light to medium gray, fine to medium crystalline, variably
4 bedded to laminated, siliceous dolomite and dolomitic limestone that weather to a chert residuum
5 (Osborne and Szabo, 1984). The Knox Group underlies a large portion of the Pelham Range
6 area.

7
8 The Ordovician Newala and Little Oak Limestones overlie the Knox Group. The Newala
9 Limestone consists of light to dark gray, micritic, thick-bedded limestone with minor dolomite.
10 The Little Oak Limestone is comprised of dark gray, medium- to thick-bedded, fossiliferous,
11 argillaceous to silty limestone with chert nodules. These limestone units are mapped as
12 undifferentiated at FTMC and in other parts of Calhoun County. The Athens Shale overlies the
13 Ordovician limestone units. The Athens Shale consists of dark gray to black shale and
14 graptolitic shale with localized interbedded dark gray limestone (Osborne et al., 1989). These
15 units occur within an eroded "window" in the uppermost structural thrust sheet at FTMC and
16 underlie much of the developed area of the Main Post.

17
18 Other Ordovician-aged bedrock units mapped in Calhoun County include the Greensport
19 Formation, Colvin Mountain Sandstone, and Sequatchie Formation. These units consist of
20 various siltstones, sandstones, shales, dolomites, and limestones and are mapped as one
21 undifferentiated unit in some areas of Calhoun County. The only Silurian-age sedimentary
22 formation mapped in Calhoun County is the Red Mountain Formation. This unit consists of
23 interbedded red sandstone, siltstone, and shale with greenish gray to red silty and sandy
24 limestone.

25
26 The Devonian Frog Mountain Sandstone consists of sandstone and quartzitic sandstone with
27 shale interbeds, dolomudstone, and glauconitic limestone (Osborne et al., 1988). This unit
28 occurs locally in the western portion of Pelham Range.

29
30 The Mississippian Fort Payne Chert and the Maury Formation overlie the Frog Mountain
31 Sandstone and are composed of dark to light gray limestone with abundant chert nodules and
32 greenish gray to grayish red phosphatic shale, with increasing amounts of calcareous chert
33 toward the upper portion of the formation (Osborne and Szabo, 1984). These units occur in the
34 northwestern portion of Pelham Range. Overlying the Fort Payne Chert is the Floyd Shale, also
35 of Mississippian age, which consists of thin-bedded, fissile brown to black shale with thin

1 intercalated limestone layers and interbedded sandstone. Osborne and Szabo (1984) reassigned
2 the Floyd Shale, which was mapped by Warman and Causey (1962) on the Main Post of FTMC,
3 to the Ordovician Athens Shale based on fossil data.

4
5 The Pennsylvanian Parkwood Formation overlies the Floyd Shale and consists of a medium to
6 dark gray, silty, clay shale and mudstone with interbedded light to medium gray, very fine to fine
7 grained, argillaceous, micaceous sandstone. Locally, the Parkwood Formation also contains
8 beds of medium to dark gray argillaceous, bioclastic to cherty limestone and beds of clayey coal
9 up to a few inches thick (Raymond et al., 1988). The Parkwood Formation in Calhoun County is
10 generally found within a structurally complex area known as the Coosa deformed belt. In the
11 deformed belt, the Parkwood Formation and Floyd Shale are mapped as undifferentiated because
12 their lithologic similarity and significant deformation make it impractical to map the contact
13 (Thomas and Drahovzal, 1974; Osborne et al., 1988). The undifferentiated Parkwood Formation
14 and Floyd Shale are found throughout the western quarter of Pelham Range.

15
16 The Jacksonville thrust fault is the most significant structural geologic feature in the vicinity of
17 the Main Post of FTMC, both for its role in determining the stratigraphic relationships in the area
18 and for its contribution to regional water supplies. The trace of the fault extends northeastward
19 for approximately 39 miles between Bynum, Alabama, and Piedmont, Alabama. The fault is
20 interpreted as a major splay of the Pell City fault (Osborne and Szabo, 1984). The Ordovician
21 sequence that makes up the Eden thrust sheet is exposed at FTMC through an eroded window, or
22 fenster, in the overlying thrust sheet. Rocks within the window display complex folding, with
23 the folds being overturned and tight to isoclinal. The carbonates and shales locally exhibit well-
24 developed cleavage (Osborne and Szabo, 1984). The FTMC window is framed on the northwest
25 by the Rome Formation; north by the Conasauga Formation; northeast, east, and southwest by
26 the Shady Dolomite; and southeast and southwest by the Chilhowee Group (Osborne et al.,
27 1997). Two small klippen of the Shady Dolomite, bounded by the Jacksonville fault, have been
28 recognized adjacent to the Pell City fault at the FTMC window (Osborne et al., 1997).

29
30 The Pell City fault serves as a fault contact between the bedrock within the FTMC window and
31 the Rome and Conasauga Formations. The trace of the Pell City fault is also exposed
32 approximately nine miles west of the FTMC window on Pelham Range, where it traverses
33 northeast to southwest across the western quarter of Pelham Range. Here, the trace of the Pell
34 City fault marks the boundary between the Pell City thrust sheet and the Coosa deformed belt.

1 The eastern three quarters of the Pelham Range are located within the Pell City thrust sheet,
2 while the remaining western quarter of Pelham is located within the Coosa deformed belt. The
3 Pell City thrust sheet is a large-scale thrust sheet containing Cambrian and Ordovician rocks and
4 is relatively less structurally complex than the Coosa deformed belt (Thomas and Neathery,
5 1982). The Pell City thrust sheet is exposed between the traces of the Jacksonville and Pell City
6 faults along the western boundary of the FTMC window and along the trace of the Pell City fault
7 on Pelham Range (Thomas and Neathery, 1982; Osborne et al., 1988). The Coosa deformed belt
8 is a narrow northeast-to-southwest-trending linear zone of complex structure (approximately 5 to
9 20 miles wide and approximately 90 miles long) consisting mainly of thin imbricate thrust slices.
10 The structure within these imbricate thrust slices is often internally complicated by small-scale
11 folding and additional thrust faults (Thomas and Drahovzal, 1974).

13 **4.4.2 Site Geology**

14 One soil type and one miscellaneous land type are mapped at Parcel 233(7). The Anniston and
15 Allen gravelly loam is mapped across the majority of the parcel with the exception of the
16 southeast corner, which is mapped as the Stony Rough Land sandstone. The Anniston and Allen
17 gravelly loam is developed in old alluvium on the foot slopes and alluvial or colluvial fans at the
18 base of large hills in the region. The surface soil ranges in color from very dark grayish brown to
19 dark reddish gray and dark reddish brown. The subsoil consists of a dark reddish gray and dark
20 reddish brown clay or silty clay loam. The Stony Rough Land sandstone miscellaneous land
21 type is found in rugged areas with steep relief where outcrops of sandstone and quartzite bedrock
22 are common. The soil material consists of a thin veneer of loose rock fragments and scattered
23 patches of sandy soil (U.S. Department of Agriculture [USDA], 1961).

25 Parcel 233(7) is located approximately 150 feet north of the Jacksonville fault within the
26 southwestern portion of the FTMC geologic window. The site is underlain by the
27 undifferentiated Floyd and Athens Shale and the undifferentiated Little Oak and Newala
28 Limestone (Figure 4-2).

30 Geologic data collected during hollow-stem auger and air-rotary drilling show alluvial soils
31 underlying Parcel 233(7). These soils range in color from yellowish orange to reddish brown to
32 brown to brownish gray and are comprised of varying combinations of gravel, sand, silt and clay.
33 The gravel found within these soils are generally sub-rounded to angular and are comprised of
34 shale, sandstone, quartzite, and chert.




Figure 4-2

Site Geologic Map

Fill Area West of Range 19
Parcel 233(7)
Fort McClellan, Alabama

Legend

Parcel Boundary

Roads

Streams (dashed where intermittent)

Topographic Contours
(Contour Interval - 25 Feet)

Monitoring Well

Geology

MOfa

Mississippian/Ordovician - Floyd and Athens Shale, undifferentiated

Oln

Ordovician - Little Oak and Newala Limestones, undifferentiated

€s

Cambrian - Shady Dolomite

Thrust Fault (dashed where inferred; barbs on upper plate)

10000100 Feet

NAD83 State Plane Coordinates

N

Shaw

Shaw Environmental, Inc.

U.S. Army Corps of Engineers
Mobile District

Contract No. DACA21-96-D-0018

Geologic Features shown in approximate location.

Revised from Osborne, W.E., et al, 1997, Preliminary Geologic Map of the Anniston 7.5' Quadrangle, Calhoun County, Alabama, Geological Survey of Alabama.

1 Bedrock was encountered at all four monitoring wells at Parcel 233(7). Weathered brown to
2 black shale consistent with the undifferentiated Floyd and Athens Shale was encountered at
3 monitoring wells PPMP-233-GP03, PPMP-233-GP04, and PPMP-233-GP05. Weathered gray
4 limestone, consistent with the undifferentiated Newala and Little Oak Limestone, was
5 encountered at monitoring well PPMP-233-GP06. Appendix D contains the boring logs and well
6 completion diagrams.

7 8 **4.5 Site Hydrology**

9 10 **4.5.1 Surface Hydrology**

11 Precipitation in the form of rainfall averages about 53 inches annually in Anniston, Alabama,
12 with infiltration rates annually exceeding evapotranspiration rates (U.S. Department of
13 Commerce, 1998). The majority of the FTMC Main Post, including Parcel 233(7), is located
14 within the Cane Creek Drainage Basin. Named tributaries to Cane Creek on the Main Post
15 include Cave Creek, Ingram Creek, Remount Creek, and the South Branch of Cane Creek.
16 These waterways flow in a general northwest to westerly direction, emptying into Cane Creek
17 within the confines of the Main Post, with the exception of Cave Creek, which occurs as a
18 separate drainage basin on post. Cave Creek joins Cane Creek approximately 1 mile west of
19 FTMC. Cane Creek then continues in a westerly direction emptying into the Coosa River along
20 the western boundary of Calhoun County.


21
22 Parcel 233(7) ranges in elevation from approximately 820 to 835 feet amsl and the ground
23 surface slopes to the north. An intermittent tributary to Remount Creek is located along the
24 northern boundary of the parcel and flows to the northeast. Remount Creek is located
25 approximately 500 feet east of the site and flows to the north. Surface runoff from the site
26 follows the topography to the north, emptying into the tributary to Remount Creek, which joins
27 Remount Creek approximately 1,100 feet northeast of the parcel.

28 29 **4.5.2 Hydrogeology**

30 Shaw installed four permanent monitoring wells at the Fill Area West of Range 19 in February
31 and March 2000. During well installation activities, groundwater was encountered at between
32 758 to 777 feet amsl, which was at or just above the soil bedrock contact. During well
33 development in April and May 2000, PPMP-233-GP06 was dry and during sampling in July
34 2000 only PPMP-233-GP04 produced sufficient water to be sampled.

1 Static groundwater levels were measured in monitoring wells in the vicinity of Parcel 233(7) as
2 summarized in Table 3-6. Groundwater elevations were calculated by measuring the depth to
3 groundwater relative to the surveyed top-of-casing elevations. A groundwater flow map
4 constructed using the June 2001 data is shown on Figure 4-3. Based on these water level data,
5 groundwater elevations correspond with topography and flow direction across the site is to the
6 northeast towards Remount Creek.

dbomar
c:\cadd\design\796886es.230
9/21/2004 8:20:57 AM
STARTING DATE: 09/16/04
DATE LAST REV.:
DRAWN BY: D. BOMAR
ENGR. CHK. BY: S. MORAN
DRAFT. CHK. BY:
PROJ. MGR.: J. YACOB
PROJ. NO.: 796886
INITIATOR: B. HEDBERG
DWG. NO.: ... \796886es.230



- ### LEGEND
- UNIMPROVED ROADS
 - PAVED ROADS
 - BUILDING
 - FORMER BUILDING
 - TOPOGRAPHIC CONTOUR
(CONTOUR INTERVAL - 25 FOOT)
 - GROUNDWATER ELEVATION CONTOUR
(DASHED WHERE INFERRED)
 - (788.15) GROUNDWATER ELEVATION (FT MSL)
(JUNE 11, 2001)
 - G.W. FLOW GROUNDWATER FLOW DIRECTION
 - PARCEL BOUNDARY
 - SURFACE DRAINAGE / CREEK
W/FLOW DIRECTION
 - MANMADE SURFACE DRAINAGE
FEATURE W/FLOW DIRECTION
 - UTILITY POLE
 - MONITORING WELL (DRY) / SURFACE AND
SUBSURFACE SOIL LOCATION
 - MONITORING WELL /GROUNDWATER,
SURFACE AND SUBSURFACE
SAMPLE LOCATION

FIGURE 4-3
GROUNDWATER ELEVATION MAP
FILL AREA WEST OF RANGE 19
PARCEL 233(7)

U. S. ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
FORT McCLELLAN
CALHOUN COUNTY, ALABAMA
Contract No. DACA21-96-D-0018



5.0 Summary of Analytical Results

The results of the chemical analyses of samples collected at the Fill Area West of Range 19, Parcel 233(7), indicate that metals, VOCs, SVOCs, and pesticides were detected in site media. To evaluate whether the detected constituents present an unacceptable risk to human health and the environment, the analytical results were compared to SSSLs and ESVs for FTMC. The SSSLs and ESVs were developed by Shaw for human health and ecological risk evaluations as part of the ongoing SIs being performed under the BRAC Environmental Restoration Program at FTMC.

Metals concentrations exceeding the SSSLs and ESVs were subsequently compared to metals background screening values to determine if the metals concentrations are within natural background concentrations (SAIC, 1998). Site metals data were further evaluated using statistical and geochemical methods to determine if the metals were site related (Appendix J).

The following sections and Tables 5-1 through 5-4 summarize the results of the comparison of detected constituents to the SSSLs, ESVs, and background screening values. Complete analytical results are presented in Appendix H.

5.1 Surface and Depositional Soil Analytical Results

Six surface soil samples and one depositional soil sample were collected for chemical analysis at the Fill Area West of Range 19, Parcel 233(7). Surface and depositional soil samples were collected from the uppermost foot of soil at the locations shown on Figure 3-1. Analytical results were compared to residential human health SSSLs, ESVs, and background screening values, as presented in Table 5-1.

Metals. A total of 19 metals were detected in the surface and depositional soil samples. Six metals (aluminum, arsenic, barium, iron, manganese, and thallium) were detected at concentrations exceeding SSSLs. These metals results, however, were below their respective background concentrations except for the following two metals:

- Barium (1,820 milligrams per kilogram [mg/kg]) exceeded its SSSL (547 mg/kg) and background (124 mg/kg) at sample location PPMP-233-GP06.
- Manganese (2,340 to 9,070 mg/kg) exceeded its SSSL (363 mg/kg) and background (1,579 mg/kg) at sample locations PPMP-233-GP02, PPMP-233-GP03, PPMP-233-GP04, and PPMP-233-GP06.

Table 5-1

Surface and Depositional Soil Analytical Results
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama

(Page 1 of 4)

Sample Location Sample Number Sample Date					PPMP-233-DEP01 KZ0015 2-Jun-00					PPMP-233-GP01 KZ0001 8-Feb-00					PPMP-233-GP02 KZ0005 21-Feb-00				
Parameter	Units	BKG ^a	SSSL ^b	ESV ^b	Result	Qual	>BKG	>SSSL	>ESV	Result	Qual	>BKG	>SSSL	>ESV	Result	Qual	>BKG	>SSSL	>ESV
METALS																			
Aluminum	mg/kg	1.63E+04	7.80E+03	5.00E+01	8.29E+03			YES	YES	8.35E+03			YES	YES	1.22E+04	J		YES	YES
Arsenic	mg/kg	1.37E+01	4.26E-01	1.00E+01	9.50E+00			YES		4.30E+00			YES		6.80E+00	J		YES	
Barium	mg/kg	1.24E+02	5.47E+02	1.65E+02	5.71E+01					7.63E+01					1.44E+02	J	YES		
Beryllium	mg/kg	8.00E-01	9.60E+00	1.10E+00	7.70E-01					5.40E-01	J				1.70E+00	J	YES		YES
Calcium	mg/kg	1.72E+03	NA	NA	8.16E+02					2.45E+02	J				2.69E+02	J			
Chromium	mg/kg	3.70E+01	2.32E+01	4.00E-01	1.70E+01				YES	1.10E+01	J			YES	1.14E+01	J			YES
Cobalt	mg/kg	1.52E+01	4.68E+02	2.00E+01	1.09E+01					7.90E+00					3.05E+01	J	YES		YES
Copper	mg/kg	1.27E+01	3.13E+02	4.00E+01	1.62E+01		YES			6.80E+00	J				1.82E+01	J	YES		
Iron	mg/kg	3.42E+04	2.34E+03	2.00E+02	3.21E+04			YES	YES	1.31E+04			YES	YES	2.07E+04	J		YES	YES
Lead	mg/kg	4.01E+01	4.00E+02	5.00E+01	1.49E+01					1.13E+01					1.83E+01	J			
Magnesium	mg/kg	1.03E+03	NA	4.40E+05	5.25E+02	J				2.44E+02	J				3.59E+02	J			
Manganese	mg/kg	1.58E+03	3.63E+02	1.00E+02	5.59E+02			YES	YES	7.84E+02			YES	YES	3.82E+03	J	YES	YES	YES
Mercury	mg/kg	8.00E-02	2.33E+00	1.00E-01	3.00E-02	J				3.40E-02	J				8.50E-02		YES		
Nickel	mg/kg	1.03E+01	1.54E+02	3.00E+01	1.11E+01		YES			6.80E+00					1.91E+01	J	YES		
Potassium	mg/kg	8.00E+02	NA	NA	7.10E+02					2.51E+02	J				3.96E+02	J			
Silver	mg/kg	3.60E-01	3.91E+01	2.00E+00	ND					ND					ND				
Thallium	mg/kg	3.43E+00	5.08E-01	1.00E+00	9.70E-01	B		YES		6.80E-01	J		YES		ND				
Vanadium	mg/kg	5.88E+01	5.31E+01	2.00E+00	3.31E+01				YES	1.70E+01				YES	2.12E+01	J			YES
Zinc	mg/kg	4.06E+01	2.34E+03	5.00E+01	3.19E+01					1.84E+01					3.97E+01	J			
VOLATILE ORGANIC COMPOUNDS																			
1,1,1-Trichloroethane	mg/kg	NA	1.55E+03	1.00E-01	ND					1.10E-03	J				ND				
Acetone	mg/kg	NA	7.76E+02	2.50E+00	ND					1.10E+00	J				1.30E-02	J			
Cumene	mg/kg	NA	7.77E+02	NA	ND					ND					5.80E-03	J			
Methylene chloride	mg/kg	NA	8.41E+01	2.00E+00	2.20E-03	B				3.10E-03	B				4.50E-03	B			
Naphthalene	mg/kg	3.30E-02	1.55E+02	1.00E-01	ND					ND					ND				
Styrene	mg/kg	NA	1.55E+03	1.00E-01	ND					ND					ND				
Trichlorofluoromethane	mg/kg	NA	2.33E+03	1.00E-01	3.00E-03	J				ND					ND				
p-Cymene	mg/kg	NA	1.55E+03	NA	ND					ND					1.30E-03	J			
SEMIVOLATILE ORGANIC COMPOUNDS																			
Benzo(ghi)perylene	mg/kg	9.55E-01	2.32E+02	1.19E+02	ND					6.50E-02	J				ND				
Bis(2-Ethylhexyl)phthalate	mg/kg	NA	4.52E+01	9.30E-01	ND					4.30E-02	J				6.30E-02	B			
PESTICIDES																			
Endosulfan II	mg/kg	NA	4.66E+01	1.19E-01	ND					ND					ND				

Table 5-1

Surface and Depositional Soil Analytical Results
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama

(Page 2 of 4)

Sample Location Sample Number Sample Date					PPMP-233-GP03 KZ0007 21-Feb-00					PPMP-233-GP04 KZ0009 22-Feb-00				
Parameter	Units	BKG ^a	SSSL ^b	ESV ^b	Result	Qual	>BKG	>SSSL	>ESV	Result	Qual	>BKG	>SSSL	>ESV
METALS														
Aluminum	mg/kg	1.63E+04	7.80E+03	5.00E+01	1.14E+04	J		YES	YES	1.08E+04	J		YES	YES
Arsenic	mg/kg	1.37E+01	4.26E-01	1.00E+01	8.90E+00	J		YES		6.00E+00	J		YES	
Barium	mg/kg	1.24E+02	5.47E+02	1.65E+02	1.45E+02	J	YES			1.49E+02	J	YES		
Beryllium	mg/kg	8.00E-01	9.60E+00	1.10E+00	1.50E+00	J	YES		YES	1.30E+00	J	YES		YES
Calcium	mg/kg	1.72E+03	NA	NA	1.76E+02	J				4.74E+02	J			
Chromium	mg/kg	3.70E+01	2.32E+01	4.00E-01	1.78E+01	J			YES	2.14E+01	J			YES
Cobalt	mg/kg	1.52E+01	4.68E+02	2.00E+01	2.56E+01	J	YES		YES	1.52E+01	J	YES		
Copper	mg/kg	1.27E+01	3.13E+02	4.00E+01	1.22E+01	J				1.00E+01	J			
Iron	mg/kg	3.42E+04	2.34E+03	2.00E+02	2.86E+04	J		YES	YES	2.23E+04	J		YES	YES
Lead	mg/kg	4.01E+01	4.00E+02	5.00E+01	1.67E+01	J				1.91E+01	J			
Magnesium	mg/kg	1.03E+03	NA	4.40E+05	3.29E+02	J				4.34E+02	J			
Manganese	mg/kg	1.58E+03	3.63E+02	1.00E+02	3.38E+03	J	YES	YES	YES	2.34E+03	J	YES	YES	YES
Mercury	mg/kg	8.00E-02	2.33E+00	1.00E-01	5.50E-02					6.90E-02				
Nickel	mg/kg	1.03E+01	1.54E+02	3.00E+01	1.93E+01	J	YES			1.20E+01	J	YES		
Potassium	mg/kg	8.00E+02	NA	NA	5.43E+02	J				5.34E+02	J			
Silver	mg/kg	3.60E-01	3.91E+01	2.00E+00	ND					ND				
Thallium	mg/kg	3.43E+00	5.08E-01	1.00E+00	ND					ND				
Vanadium	mg/kg	5.88E+01	5.31E+01	2.00E+00	2.62E+01	J			YES	2.03E+01	J			YES
Zinc	mg/kg	4.06E+01	2.34E+03	5.00E+01	3.46E+01	J				2.55E+01	J			
VOLATILE ORGANIC COMPOUNDS														
1,1,1-Trichloroethane	mg/kg	NA	1.55E+03	1.00E-01	ND					1.10E-03	J			
Acetone	mg/kg	NA	7.76E+02	2.50E+00	4.50E-02	J				4.70E-01	J			
Cumene	mg/kg	NA	7.77E+02	NA	8.40E-04	J				ND				
Methylene chloride	mg/kg	NA	8.41E+01	2.00E+00	5.30E-03	B				5.60E-03	B			
Naphthalene	mg/kg	3.30E-02	1.55E+02	1.00E-01	ND					ND				
Styrene	mg/kg	NA	1.55E+03	1.00E-01	ND					1.10E-03	J			
Trichlorofluoromethane	mg/kg	NA	2.33E+03	1.00E-01	ND					ND				
p-Cymene	mg/kg	NA	1.55E+03	NA	ND					2.20E-03	J			
SEMIVOLATILE ORGANIC COMPOUNDS														
Benzo(ghi)perylene	mg/kg	9.55E-01	2.32E+02	1.19E+02	ND					ND				
Bis(2-Ethylhexyl)phthalate	mg/kg	NA	4.52E+01	9.30E-01	5.30E-02	B				1.10E-01	B			
PESTICIDES														
Endosulfan II	mg/kg	NA	4.66E+01	1.19E-01	ND					ND				

Table 5-1

Surface and Depositional Soil Analytical Results
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama

(Page 3 of 4)

Sample Location Sample Number Sample Date					PPMP-233-GP05 KZ0011 8-Feb-00					PPMP-233-GP06 KZ0013 23-Feb-00				
Parameter	Units	BKG ^a	SSSL ^b	ESV ^b	Result	Qual	>BKG	>SSSL	>ESV	Result	Qual	>BKG	>SSSL	>ESV
METALS														
Aluminum	mg/kg	1.63E+04	7.80E+03	5.00E+01	1.23E+04			YES	YES	7.61E+03	J			YES
Arsenic	mg/kg	1.37E+01	4.26E-01	1.00E+01	8.20E+00			YES		8.10E+00	J		YES	
Barium	mg/kg	1.24E+02	5.47E+02	1.65E+02	5.43E+01					1.82E+03	J	YES	YES	YES
Beryllium	mg/kg	8.00E-01	9.60E+00	1.10E+00	9.20E-01		YES			1.60E+00	J	YES		YES
Calcium	mg/kg	1.72E+03	NA	NA	5.69E+01	J				1.61E+02	J			
Chromium	mg/kg	3.70E+01	2.32E+01	4.00E-01	2.15E+01	J			YES	1.61E+01	J			YES
Cobalt	mg/kg	1.52E+01	4.68E+02	2.00E+01	1.91E+01		YES			1.20E+02	J	YES		YES
Copper	mg/kg	1.27E+01	3.13E+02	4.00E+01	1.84E+01	J	YES			2.40E+01	J	YES		
Iron	mg/kg	3.42E+04	2.34E+03	2.00E+02	2.94E+04			YES	YES	2.85E+04	J		YES	YES
Lead	mg/kg	4.01E+01	4.00E+02	5.00E+01	1.40E+01					4.85E+01	J	YES		
Magnesium	mg/kg	1.03E+03	NA	4.40E+05	4.21E+02	J				2.13E+02	J			
Manganese	mg/kg	1.58E+03	3.63E+02	1.00E+02	1.16E+03			YES	YES	9.07E+03	J	YES	YES	YES
Mercury	mg/kg	8.00E-02	2.33E+00	1.00E-01	5.10E-02					4.60E-02				
Nickel	mg/kg	1.03E+01	1.54E+02	3.00E+01	1.47E+01		YES			2.11E+01	J	YES		
Potassium	mg/kg	8.00E+02	NA	NA	5.83E+02	J				2.86E+02	J			
Silver	mg/kg	3.60E-01	3.91E+01	2.00E+00	ND					2.40E-01	J			
Thallium	mg/kg	3.43E+00	5.08E-01	1.00E+00	ND					ND				
Vanadium	mg/kg	5.88E+01	5.31E+01	2.00E+00	3.03E+01				YES	3.57E+01	J			YES
Zinc	mg/kg	4.06E+01	2.34E+03	5.00E+01	4.46E+01		YES			4.28E+01	J	YES		
VOLATILE ORGANIC COMPOUNDS														
1,1,1-Trichloroethane	mg/kg	NA	1.55E+03	1.00E-01	9.50E-04	J				6.90E-04	J			
Acetone	mg/kg	NA	7.76E+02	2.50E+00	2.90E+00	J			YES	4.50E-02	B			
Cumene	mg/kg	NA	7.77E+02	NA	4.80E-03	J				ND				
Methylene chloride	mg/kg	NA	8.41E+01	2.00E+00	3.00E-03	B				4.90E-03	B			
Naphthalene	mg/kg	3.30E-02	1.55E+02	1.00E-01	ND					8.80E-04	J			
Styrene	mg/kg	NA	1.55E+03	1.00E-01	ND					ND				
Trichlorofluoromethane	mg/kg	NA	2.33E+03	1.00E-01	ND					ND				
p-Cymene	mg/kg	NA	1.55E+03	NA	5.20E-03	J				ND				
SEMIVOLATILE ORGANIC COMPOUNDS														
Benzo(ghi)perylene	mg/kg	9.55E-01	2.32E+02	1.19E+02	ND					ND				
Bis(2-Ethylhexyl)phthalate	mg/kg	NA	4.52E+01	9.30E-01	ND					8.90E-02	B			
PESTICIDES														
Endosulfan II	mg/kg	NA	4.66E+01	1.19E-01	6.70E-04	J				ND				

Table 5-1

**Surface and Depositional Soil Analytical Results
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama**

(Page 4 of 4)

Analyses performed using U.S. Environmental Protection Agency (EPA) SW-846 analytical methods.

^a Bkg - Background. Concentration listed is two times (2x) the arithmetic mean of background metals concentration given in SAIC (1998), *Final Background Metals Survey Report, Fort McClellan, Calhoun County, Alabama*, July.

For SVOCs, value listed is the background screening criterion for soils adjacent to asphalt as given in IT (2000), *Final Human Health and Ecological Screening Values and PAH Background Summary Report, Fort McClellan, Calhoun County, Alabama*, July.

^b Residential human health site-specific screening level (SSSL) and ecological screening value (ESV) as given in IT (2000).

B - Analyte detected in laboratory or field blank at concentration greater than the reporting limit.

J - Compound was positively identified; reported value is an estimated concentration.

mg/kg - Milligrams per kilogram.

NA - Not available.

ND - Not detected.

Qual - Data validation qualifier.

Table 5-2

Subsurface Soil Analytical Results
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama

(Page 1 of 3)

Sample Location Sample Number Sample Date Sample Depth (Feet)				PPMP-233-GP01 KZ0004 8-Feb-00 10 - 12				PPMP-233-GP02 KZ0006 21-Feb-00 10 - 12				PPMP-233-GP03 KZ0008 21-Feb-00 10 - 12			
Parameter	Units	BKG ^a	SSSL ^b	Result	Qual	>BKG	>SSSL	Result	Qual	>BKG	>SSSL	Result	Qual	>BKG	>SSSL
METALS															
Aluminum	mg/kg	1.36E+04	7.80E+03	6.04E+03				4.03E+03	J			4.34E+03	J		
Arsenic	mg/kg	1.83E+01	4.26E-01	1.34E+01			YES	1.01E+01	J		YES	7.90E+00	J		YES
Barium	mg/kg	2.34E+02	5.47E+02	2.07E+01	J			5.33E+01	J			1.06E+03	J	YES	YES
Beryllium	mg/kg	8.60E-01	9.60E+00	1.10E+00		YES		1.80E+00	J	YES		4.60E+00	J	YES	
Cadmium	mg/kg	2.20E-01	6.25E+00	ND				ND				1.20E+00	J	YES	
Calcium	mg/kg	6.37E+02	NA	3.43E+01	B			2.65E+01	B			4.11E+01	B		
Chromium	mg/kg	3.83E+01	2.32E+01	1.70E+01	J			7.10E+00	J			9.10E+00	J		
Cobalt	mg/kg	1.75E+01	4.68E+02	5.50E+00	J			4.22E+01	J	YES		1.13E+02	J	YES	
Copper	mg/kg	1.94E+01	3.13E+02	1.96E+01	J	YES		2.41E+01	J	YES		2.09E+01	J	YES	
Iron	mg/kg	4.48E+04	2.34E+03	2.79E+04			YES	3.02E+04	J		YES	7.98E+04	J	YES	YES
Lead	mg/kg	3.85E+01	4.00E+02	1.68E+01				2.47E+01	J			1.11E+01	J		
Magnesium	mg/kg	7.66E+02	NA	2.10E+02	J			1.28E+02	J			1.04E+02	J		
Manganese	mg/kg	1.36E+03	3.63E+02	2.65E+02				1.24E+03	J		YES	2.02E+04	J	YES	YES
Mercury	mg/kg	7.00E-02	2.33E+00	2.40E-02	J			4.80E-02				8.80E-02		YES	
Nickel	mg/kg	1.29E+01	1.54E+02	1.86E+01		YES		3.00E+01	J	YES		8.35E+01	J	YES	
Potassium	mg/kg	7.11E+02	NA	4.08E+02	J			6.07E+02	J			1.76E+03	J	YES	
Selenium	mg/kg	4.70E-01	3.91E+01	ND				ND				5.00E-01	J	YES	
Silver	mg/kg	2.40E-01	3.91E+01	ND				ND				3.90E-01	J	YES	
Thallium	mg/kg	1.40E+00	5.08E-01	7.70E-01	J		YES	8.40E-01	B		YES	ND			
Vanadium	mg/kg	6.49E+01	5.31E+01	2.76E+01				1.67E+01	J			1.37E+01	J		
Zinc	mg/kg	3.49E+01	2.34E+03	1.37E+02		YES		9.66E+01	J	YES		1.48E+02	J	YES	
SEMIVOLATILE ORGANIC COMPOUNDS															
Bis(2-Ethylhexyl)phthalate	mg/kg	NA	4.52E+01	ND				6.00E-02	B			5.00E-02	B		
Di-n-octyl phthalate	mg/kg	NA	1.56E+02	ND				ND				ND			
VOLATILE ORGANIC COMPOUNDS															
1,1,1-Trichloroethane	mg/kg	NA	1.55E+03	1.10E-03	J			8.80E-04	J			ND			
Acetone	mg/kg	NA	7.76E+02	ND				1.50E-02	J			ND			
Methylene chloride	mg/kg	NA	8.41E+01	3.00E-03	B			5.80E-03	B			5.40E-03	B		
Trichlorofluoromethane	mg/kg	NA	2.33E+03	3.00E-03	J			ND				ND			

Table 5-2

**Subsurface Soil Analytical Results
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama**

(Page 2 of 3)

Sample Location Sample Number Sample Date Sample Depth (Feet)				PPMP-233-GP04 KZ0010 22-Feb-00 10 - 12				PPMP-233-GP05 KZ0012 8-Feb-00 10 - 12				PPMP-233-GP06 KZ0014 24-Feb-00 8 - 10			
Parameter	Units	BKG ^a	SSSL ^b	Result	Qual	>BKG	>SSSL	Result	Qual	>BKG	>SSSL	Result	Qual	>BKG	>SSSL
METALS															
Aluminum	mg/kg	1.36E+04	7.80E+03	1.22E+04	J		YES	3.33E+03				8.10E+03	J		YES
Arsenic	mg/kg	1.83E+01	4.26E-01	5.80E+00	J		YES	7.40E+00			YES	1.04E+01	J		YES
Barium	mg/kg	2.34E+02	5.47E+02	3.55E+01	J			2.08E+01	J			5.58E+01	J		
Beryllium	mg/kg	8.60E-01	9.60E+00	6.60E-01	B			3.20E+00		YES		8.20E-01	J		
Cadmium	mg/kg	2.20E-01	6.25E+00	ND				ND				ND			
Calcium	mg/kg	6.37E+02	NA	2.68E+01	B			1.45E+01	B			6.97E+01	J		
Chromium	mg/kg	3.83E+01	2.32E+01	2.50E+01	J		YES	9.70E+00	J			2.32E+01	J		YES
Cobalt	mg/kg	1.75E+01	4.68E+02	2.06E+01	J	YES		1.09E+01				1.53E+01	J		
Copper	mg/kg	1.94E+01	3.13E+02	3.22E+01	J	YES		2.99E+01	J	YES		2.99E+01	J	YES	
Iron	mg/kg	4.48E+04	2.34E+03	4.56E+04	J	YES	YES	3.76E+04			YES	3.63E+04	J		YES
Lead	mg/kg	3.85E+01	4.00E+02	1.80E+01	J			1.15E+01				1.45E+01	J		
Magnesium	mg/kg	7.66E+02	NA	1.97E+02	J			2.22E+02	J			3.12E+02	J		
Manganese	mg/kg	1.36E+03	3.63E+02	3.34E+02	J			3.65E+02			YES	6.94E+02	J		YES
Mercury	mg/kg	7.00E-02	2.33E+00	5.10E-02				4.30E-02				4.20E-02			
Nickel	mg/kg	1.29E+01	1.54E+02	9.50E+00	J			3.91E+01		YES		1.66E+01	J	YES	
Potassium	mg/kg	7.11E+02	NA	6.02E+02	J			9.87E+02		YES		1.33E+03	J	YES	
Selenium	mg/kg	4.70E-01	3.91E+01	ND				ND				ND			
Silver	mg/kg	2.40E-01	3.91E+01	ND				ND				ND			
Thallium	mg/kg	1.40E+00	5.08E-01	9.60E-01	B		YES	8.30E-01	J		YES	8.50E-01	B		YES
Vanadium	mg/kg	6.49E+01	5.31E+01	4.40E+01	J			1.58E+01				3.27E+01	J		
Zinc	mg/kg	3.49E+01	2.34E+03	2.59E+01	J			1.27E+02		YES		3.62E+01	J	YES	
SEMIVOLATILE ORGANIC COMPOUNDS															
Bis(2-Ethylhexyl)phthalate	mg/kg	NA	4.52E+01	1.20E-01	B			ND				5.80E-01	B		
Di-n-octyl phthalate	mg/kg	NA	1.56E+02	ND				ND				1.90E-01	J		
VOLATILE ORGANIC COMPOUNDS															
1,1,1-Trichloroethane	mg/kg	NA	1.55E+03	ND				1.40E-03	J			8.40E-04	J		
Acetone	mg/kg	NA	7.76E+02	ND				ND				7.80E-03	B		
Methylene chloride	mg/kg	NA	8.41E+01	4.00E-03	B			3.90E-03	B			5.60E-03	B		
Trichlorofluoromethane	mg/kg	NA	2.33E+03	ND				ND				ND			

Table 5-2

Subsurface Soil Analytical Results Fill Area West of Range 19, Parcel 233(7) Fort McClellan, Calhoun County, Alabama

(Page 3 of 3)

Analyses performed using U.S. Environmental Protection Agency (EPA) SW-846 analytical methods.

^a Bkg - Background. Concentration listed is two times (2x) the arithmetic mean of background metals concentration given in SAIC (1998), *Final Background Metals Survey Report, Fort McClellan, Calhoun County, Alabama*, July.

^b Residential human health site-specific screening level (SSSL) as given in IT (2000), *Final Human Health and Ecological Screening Values and PAH Background Summary Report, Fort McClellan, Calhoun County, Alabama*, July.

B - Analyte detected in laboratory or field blank at concentration greater than the reporting limit (and greater than zero).

J - Compound was positively identified; reported value is an estimated concentration.

mg/kg - Milligrams per kilogram.

NA - Not available.

ND - Not detected.

Qual - Data validation qualifier.

Table 5-3

Groundwater Analytical Results
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama

Sample Location Sample Number Sample Date				PPMP-233-GP04 KZ3004 14-Jul-00			
Parameter	Units	BKG ^a	SSSL ^b	Result	Qual	>BKG	>SSSL
METALS							
Aluminum	mg/L	2.34E+00	1.56E+00	4.46E-01	B		
Barium	mg/L	1.27E-01	1.10E-01	1.30E-02	J		
Calcium	mg/L	5.65E+01	NA	7.16E-01	J		
Chromium	mg/L	NA	4.69E-03	1.30E-01	J		YES
Cobalt	mg/L	2.34E-02	9.39E-02	1.07E-02	J		
Iron	mg/L	7.04E+00	4.69E-01	2.09E+00	J		YES
Magnesium	mg/L	2.13E+01	NA	2.74E-01	B		
Manganese	mg/L	5.81E-01	7.35E-02	1.91E-01			YES
Mercury	mg/L	NA	4.69E-04	9.90E-05	B		
Nickel	mg/L	NA	3.13E-02	7.04E-02	J		YES
Potassium	mg/L	7.20E+00	NA	1.22E+00	J		
Sodium	mg/L	1.48E+01	NA	1.75E+00	J		
Zinc	mg/L	2.20E-01	4.69E-01	1.52E-02	J		
PESTICIDES							
4,4'-DDD	mg/L	NA	1.83E-04	7.40E-05	J		
Aldrin	mg/L	NA	3.90E-06	3.40E-05	J		YES
Endosulfan II	mg/L	NA	9.35E-03	1.60E-05	J		
delta-BHC	mg/L	NA	4.49E-04	3.30E-05	J		

Analyses performed using U.S. Environmental Protection Agency (EPA) SW-846 analytical methods.

^a Bkg - Background. Concentration listed is two times (2x) the arithmetic mean of background metals concentration given in Science Applications International Corporation (1998), *Final Background Metals Survey Report, Fort McClellan, Alabama, July*.

^b Residential human health site-specific screening level (SSSL) as given in IT (2000), *Final Human Health and Ecological Screening Values and PAH Background Summary Report, Fort McClellan, Calhoun County, Alabama, July*.

B - Analyte detected in laboratory or field blank at concentration greater than the reporting limit.

J - Compound was positively identified; reported value is an estimated concentration.

mg/L - Milligrams per liter.

NA - Not available.

Qual - Data validation qualifier.

Table 5-4

**Chromium and Nickel Groundwater Analytical Results in Nearby Wells
Fill Area West of Range 19, Parcel 233(7)
Fort McClellan, Calhoun County, Alabama**

Well Designation Sample Number Sample Date Location Relative to Parcel 233(7)				HR-73Q-MW02 JF3002 10-May-01 400' upgradient			HR-73Q-MW03 JF3005 18-Apr-01 800' upgradient			HR-228Q-MW02 JS3002 14-May-01 400' sidegradient			HR-232QX-MW15 ECC3015 6-Jun-01 200' downgradient		
Parameter	Units	BKG ^a	SSSL ^b	Result	Qual	>SSSL	Result	Qual	>SSSL	Result	Qual	>SSSL	Result	Qual	>SSSL
METALS															
Chromium	mg/L	NA	4.69E-03	ND			ND			ND			ND		
Nickel	mg/L	NA	3.13E-02	ND			1.58E-02	B		ND			ND		

Analyses performed using U.S. Environmental Protection Agency (EPA) SW-846 analytical methods.

^a Bkg - Background. Concentration listed is two times (2x) the arithmetic mean of background metals concentration given in Science Applications International Corporation (1998), *Final Background Metals Survey Report, Fort McClellan, Alabama*, July.

^b Residential human health site-specific screening level (SSSL) as given in IT (2000), *Final Human Health and Ecological Screening Values and PAH Background Summary Report, Fort McClellan, Calhoun County, Alabama*, July.

B - Analyte detected in laboratory or field blank at concentration greater than the reporting limit.

mg/L - Milligrams per liter.

NA - Not available.

ND - Not detected.

Qual - Data validation qualifier.

The concentrations of eight metals exceeded ESVs: aluminum, barium, beryllium, chromium, cobalt, iron, manganese, and vanadium. Of these, the following metals also exceeded their respective background concentrations in one or more samples:

- Barium (1,820 mg/kg) exceeded its ESV (165 mg/kg) and background (124 mg/kg) at one sample location (PPMP-233-GP06).
- Beryllium (1.3 to 1.7 mg/kg) exceeded its ESV (1.1 mg/kg) and background (0.8 mg/kg) at four sample locations (PPMP-233-GP02, PPMP-233-GP03, PPMP-233-GP04, and PPMP-233-GP06).
- Cobalt (25.6 to 120 mg/kg) exceeded its ESV (20 mg/kg) and background (15.2 mg/kg) at three sample locations (PPMP-233-GP02, PPMP-233-GP03, and PPMP-233-GP06).
- Manganese (2,340 to 9,070 mg/kg) exceeded its ESV (100 mg/kg) and background (1,579 mg/kg) at four locations (PPMP-233-GP02, PPMP-233-GP03, PPMP-233-GP04, and PPMP-233-GP06).

Volatile Organic Compounds. A total of eight VOCs were detected in the surface and depositional soil samples: 1,1,1-trichloroethane, acetone, cumene, methylene chloride, naphthalene, p-cymene, styrene, and trichlorofluoromethane. The methylene chloride results and one acetone result were flagged with a “B” data qualifier, indicating that these compounds were also detected in an associated laboratory or field blank sample. The remaining VOC results were flagged with a “J” data qualifier, indicating that the concentrations were estimated. VOC concentrations in surface and depositional soils ranged from 0.00069 to 2.9 mg/kg.

The VOC concentrations were below SSSLs and ESVs except for one acetone result (2.9 mg/kg), which minimally exceeded its ESV (2.5 mg/kg) at sample location PPMP-233-GP05.

Semivolatile Organic Compounds. Two SVOCs were detected in the surface and depositional soil samples: the PAH compound benzo(ghi)perylene and bis(2-ethylhexyl)phthalate. Four of the five bis(2-ethylhexyl)phthalate results were flagged with a “B” data qualifier, indicating that this compound was also detected in an associated laboratory or field blank sample. The remaining bis(2-ethylhexyl)phthalate result and the single benzo(ghi)perylene result were flagged with a “J” data qualifier, indicating that the concentrations were estimated. SVOC concentrations in surface and depositional soils ranged from 0.043 to 0.11 mg/kg and all results were below SSSLs and ESVs.

1
2 **Pesticides.** One pesticide, endosulfan II, was detected in surface soil sample location PPMP-
3 233-GP05. This result was flagged with a “J” data qualifier, indicating that the concentration
4 was estimated. The endosulfan II result (0.00067 mg/kg) was well below its SSSL (46.6 mg/kg)
5 and ESV (0.119 mg/kg).

6
7 **Herbicides.** Herbicides were not detected in the surface and depositional soil samples.

8
9 **Polychlorinated Biphenyls.** PCBs were not detected in the surface and depositional soil
10 samples.

11 12 **5.2 Subsurface Soil Analytical Results**

13 Six subsurface soil samples were collected for chemical analysis at the Fill Area West of Range
14 19, Parcel 233(7). Subsurface soil samples were collected at depths greater than 1 foot bgs at the
15 locations shown on Figure 3-1. Analytical results were compared to residential human health
16 SSSLs and metals background concentrations as presented in Table 5-2.

17
18 **Metals.** A total of 21 metals were detected in the subsurface soil samples. The concentrations
19 of seven metals (aluminum, arsenic, barium, chromium, iron, manganese, and thallium)
20 exceeded SSSLs. Of these, three metals also exceeded their respective background values in one
21 or two samples as follows:

- 22
23 • Barium (1,060 mg/kg) exceeded its SSSL (547 mg/kg) and background (234
24 mg/kg) at sample location PPMP-233-GP03.
- 25
26 • Iron (45,600 and 78,900 mg/kg) exceeded its SSSL (2,345 mg/kg) and background
27 (44,817 mg/kg) at two sample locations (PPMP-233-GP03 and PPMP-233-GP04).
- 28
29 • Manganese (20,200 mg/kg) exceeded its SSSL (363 mg/kg) and background
30 (1,355 mg/kg) at sample location PPMP-233-GP03.

31
32 **Volatile Organic Compounds.** A total of four VOCs were detected in the subsurface soil
33 samples: 1,1,1-trichloroethane, acetone, methylene chloride, and trichlorofluoromethane. All the
34 VOC results were flagged with either a “B” data qualifier, indicating that these compounds were
35 also detected in an associated laboratory or field blank sample, or a “J” data qualifier, indicating
36 that the concentrations were estimated. VOC concentrations in subsurface soils ranged from
37 0.00084 to 0.1 mg/kg and all results were below SSSLs.

1 **Semivolatile Organic Compounds.** Two SVOCs (bis[2-ethylhexyl]phthalate and di-n-octyl
2 phthalate) were detected in the subsurface soil samples. The bis(2-ethylhexyl)phthalate results
3 were “B” flagged, indicating that the compound was also detected in an associated laboratory or
4 field blank sample. The single di-n-octyl phthalate result was flagged with a “J” data qualifier,
5 indicating that the concentration was estimated. All the SVOC results were below SSSLs.

6
7 **Pesticides.** Pesticides were not detected in the subsurface soil samples.

8
9 **Herbicides.** Herbicides were not detected in the subsurface soil samples.

10
11 **Polychlorinated Biphenyls.** PCBs were not detected in the subsurface soil samples.

12
13 **Explosives.** One subsurface soil sample (location PPMP-233-GP05) was analyzed for
14 explosives. Explosives were not detected in the sample.

15 16 **5.3 Groundwater Analytical Results**

17 One groundwater sample was collected at the Fill Area West of Range 19, Parcel 233(7), at the
18 location shown on Figure 3-1. Analytical results were compared to residential human health
19 SSSLs and metals background concentrations as presented in Table 5-3.

20
21 **Metals.** Thirteen metals were detected in the groundwater sample. The aluminum, magnesium,
22 and mercury results were flagged with a “B” data qualifier, indicating that these metals were also
23 detected in an associated laboratory or field blank sample. All of the other metals results except
24 manganese were “J” flagged, indicating that the concentrations were estimated. The
25 concentrations of four metals (chromium, iron, manganese, and nickel) exceeded SSSLs. The
26 iron and manganese results were below their respective background concentrations. Background
27 values for chromium and nickel were not available.

28
29 **Volatile Organic Compounds.** VOCs were not detected in the groundwater sample.

30
31 **Semivolatile Organic Compounds.** SVOCs were not detected in the groundwater sample.

32
33 **Pesticides.** Four pesticides were detected in the groundwater sample:
34 4,4-dichlorodiphenyldichloroethane (DDD), aldrin, endosulfan II, and delta-
35 hexachlorocyclohexane (BHC). All of the pesticide results were “J” flagged, indicating that the
36 concentrations were estimated. The pesticide concentrations in the sample ranged from

0.000016 to 0.000074 mg/L and were below their respective SSSLs, except for aldrin. The aldrin result (0.000034 mg/L) exceeded its SSSL (0.0000039 mg/L).

Herbicides. Herbicides were not detected in the groundwater sample.

Polychlorinated Biphenyls. PCBs were not detected in the groundwater sample.

5.4 Statistical and Geochemical Evaluation of Site Metals Data

Site metals data were further evaluated using statistical and geochemical methods to determine if the metals are site related (Appendix J). This multi-tiered approach is described in the technical memorandum "Selecting Site-Related Chemicals for Human Health and Ecological Risk Assessments for FTMC: Revision 2" (Shaw, 2003b). The statistical and geochemical evaluation determined that the metals detected in site media are present at naturally occurring levels, with the exception of chromium and nickel in the groundwater sample. The chromium and nickel results were judged to be anomalously high relative to the reference elements and may be indicative of contamination.

5.5 Additional Chromium and Nickel Groundwater Data Evaluation

To further address chromium and nickel in groundwater, groundwater data were evaluated from four additional wells that closely surround the site (as shown on Figure 3-1). Two of these wells (HR-73Q-MW02 and HR-73Q-MW03) are located upgradient approximately 400 and 800 feet of the site, respectively. One well (HR-232QX-MW15) is located downgradient at a distance of approximately 200 feet and one well (HR-228Q-MW02) is located sidegradient at a distance of approximately 400 feet.

The data from the surrounding wells indicate that chromium was not detected in any of the wells (Table 5-4). Although nickel was detected in one upgradient well (HR-73Q-MW03), the result was "B" flagged, indicating the presence of laboratory artifacts. This result was below the SSSL.

It is also worth noting that the field duplicate sample collected at PPMP-233-GP04 (data shown in Appendix H) contained considerably lower concentrations of both chromium and nickel. The estimated nickel concentration in the duplicate sample (0.0152 mg/L) was below its SSSL (0.031 mg/L) and was approximately five times lower than the concentration in the regular field sample (0.0704 mg/L). The estimated chromium concentration in the duplicate sample (0.0217 mg/L) exceeded the SSSL (0.0047 mg/L) but was approximately six times lower than the concentration in the field sample (0.13 mg/L).

6.0 Summary, Conclusions, and Recommendations

Shaw completed an SI at the Fill Area West of Range 19, Parcel 233(7), at FTMC in Calhoun County, Alabama. The SI was conducted to determine whether chemical constituents are present at the site as a result of mission-related Army activities. SI field activities consisted of the collection and analysis of six surface soil samples, one depositional soil sample, six subsurface soil samples, and one groundwater sample. In addition, four monitoring wells were installed to facilitate sample collection and to provide site-specific geological and hydrogeological characterization information. However, only one well produced sufficient groundwater for sampling during the investigation. Additional SI activities included a geophysical survey and exploratory trenching as well as a wetlands study.

The geophysical survey identified one area of anomalously high conductivity. However, exploratory trenching performed within the area did not indicate the presence of fill material. Additionally, the wetlands study concluded that wetlands are not present on or within 200 feet of Parcel 233(7).

Chemical analysis of samples collected at the site indicates that metals, VOCs, SVOCs, and pesticides were detected in site media. To evaluate whether the detected constituents pose an unacceptable risk to human health or the environment, the analytical results were compared to human health SSSLs, ESVs, and background screening values for FTMC. Additionally, site metals data were evaluated using statistical and geochemical methods to determine if the metals detected in site media were naturally occurring.

Three metals in soil (barium, iron, and manganese) and two metals in groundwater (chromium and nickel) were detected at concentrations exceeding SSSLs and background (where available) and, thus, were selected as COPCs. The statistical and geochemical evaluations determined that these metals were naturally occurring, except for chromium and nickel in groundwater. To address the presence of chromium and nickel in groundwater, groundwater data were evaluated from four additional wells that surround the site. The data from the surrounding wells indicated that chromium was not detected in any of the wells and nickel was detected in only one upgradient well (800 feet away) at a level below the SSSL. Therefore, the chromium and nickel detected in groundwater at Parcel 233(7) appear to be isolated occurrences, and are not believed to pose an unacceptable threat to human health. The pesticide aldrin was also identified as a COPC in groundwater because it was detected at an estimated concentration exceeding its SSSL.

1 An SRA was completed as part of the EE/CA for Parcel 233(7). The SRA concluded that aldrin
2 in groundwater was not a human health concern because the calculated risk was within
3 acceptable limits (IT, 2002b).

4
5 Four metals (barium, beryllium, cobalt, and manganese) were detected in surface soil at
6 concentrations exceeding ESVs and background and, thus, were selected as constituents of
7 potential ecological concern (COPEC). However, the statistical and geochemical evaluation
8 determined that these metals were all naturally occurring. The VOC acetone was also identified
9 as a COPEC in surface soil because it was detected at an estimated concentration minimally
10 exceeding its ESV in one sample. Based on the relatively small amount by which the acetone
11 result exceeded the ESV, coupled with the destruction of much of the terrestrial habitat through
12 construction of the Eastern Bypass Highway, it is concluded that acetone does not pose an
13 unacceptable threat to ecological receptors at this site. This conclusion is consistent with the
14 findings of the SLERA completed as part of the EE/CA (IT, 2002b).

15
16 Based on the results of the SI, including confirmation that fill material is not present, potential
17 historical activities at the Fill Area West of Range 19, Parcel 233(7), have not adversely
18 impacted the environment. The metals and chemical compounds detected in site media do not
19 pose an unacceptable risk to human health and the environment. Therefore, Shaw recommends
20 "No Further Action" and unrestricted land reuse with regard to CERCLA-related hazardous
21 substances at the Fill Area West of Range 19, Parcel 233(7).

7.0 References

- American Society for Testing and Materials (ASTM), 2000, *Standard Practice for Description and Identification of Soils (Visual-Manual Procedure)*, ASTM D 2488-00.
- Cloud, P. E., Jr., 1966, *Bauxite Deposits of the Anniston, Fort Payne, and Ashville Areas, Northeast Alabama*, U. S. Geological Survey Bulletin 1199-O.
- Environmental Science and Engineering, Inc. (ESE), 1998, *Final Environmental Baseline Survey, Fort McClellan, Alabama*, prepared for U.S. Army Environmental Center, Aberdeen Proving Ground, Maryland, January.
- Hunt, Roy E., 1986, *Geotechnical Engineering Techniques and Practices*, McGraw-Hill Book Co., New York.
- IT Corporation (IT), 2002a, *Draft Final Site Investigation and Fill Area Definition Report, Landfills and Fill Areas, Parcels 78(6), 79(6), 80(6), 81(5), 175(5), 230(7), 227(7), 229(7), 126(7), 233(7) and 82(7), Fort McClellan, Calhoun County, Alabama*, March.
- IT Corporation (IT), 2002b, *Draft Final Engineering Evaluation/Cost Analysis, Landfills and Fill Areas, Parcels 78(6), 79(6), 80(6), 81(5), 175(5), 230(7), 227(7), 229(7), 126(7), 233(7) and 82(7), Fort McClellan, Calhoun County, Alabama*, March.
- IT Corporation (IT), 2000, *Final Human Health and Ecological Screening Values and PAH Background Summary Report, Fort McClellan, Calhoun County, Alabama*, July.
- IT Corporation (IT), 1998a, *Final Site-Specific Field Sampling Plan and Site-Specific Safety and Health Plan Attachments, Fill Area West of Range 19, Parcel 233(7), Fort McClellan, Calhoun County, Alabama*, December.
- IT Corporation (IT), 1998b, *Final Installation-Wide Work Plan, Fort McClellan, Calhoun County, Alabama*, August.
- IT Corporation (IT), 1998c, *Final Installation-Wide Sampling and Analysis Plan, Fort McClellan, Calhoun County, Alabama*, August.
- Moser, P. H., and S.S. DeJarnette, 1992, *Groundwater Availability in Calhoun County, Alabama*, Geological Survey of Alabama Special Map 228.
- Osborne, W. E., 1999, personal communication with John Hofer, IT Corporation.
- Osborne, W. E., G. D. Irving, and W. E. Ward, 1997, *Geologic Map of the Anniston 7.5' Quadrangle, Calhoun County, Alabama*, Alabama Geologic Survey Preliminary Map, 1 sheet.
- Osborne, W. E., M. W. Szabo, C. W. Copeland, Jr., and T. L. Neathery, 1989, *Geologic Map of Alabama*, Alabama Geologic Survey Special Map 221, scale 1:500,000, 1 sheet.

Osborne, W. E., M. W. Szabo, T. L. Neathery, and C. W. Copeland, compilers, 1988, ***Geologic Map of Alabama, Northeast Sheet***, Geological Survey of Alabama Special Map 220, Scale 1:250,000.

Osborne, W. E., and M.W. Szabo, 1984, ***Stratigraphy and Structure of the Jacksonville Fault, Calhoun County, Alabama***, Alabama Geological Survey Circular 117.

Raymond, D. E., W. E. Osborne, C. W. Copeland, and T. L. Neathery, 1988, ***Alabama Stratigraphy***, Geological Survey of Alabama, Tuscaloosa, Alabama.

Science Applications International Corporation (SAIC), 1998, ***Final Background Metals Survey Report, Fort McClellan, Alabama***, July.

Shaw Environmental, Inc. (Shaw), 2003a, ***Final Wetland Determination, Landfills and Fill Areas, Fort McClellan, Calhoun County, Alabama***, April.

Shaw Environmental, Inc. (Shaw), 2003b, "Selecting Site-Related Chemicals for Human Health and Ecological Risk Assessments for FTMC: Revision 2," technical memorandum dated June 24.

Thomas, W. A., and J. A. Drahovzal, 1974, ***The Coosa Deformed Belt in the Alabama Appalachians***, Alabama Geological Society, 12th Annual Field Trip Guidebook.

Thomas, W. A., and T. L. Neathery, 1982, ***Appalachian Thrust Belts in Alabama: Tectonics and Sedimentation***, Geologic Society of America 1982 Annual Meeting, New Orleans, Louisiana, Field Trip, Alabama Geological Society Guidebook 19A.

U.S. Army Corps of Engineers (USACE), 2001a, ***Fort McClellan Archive Search Report, Conclusions and Recommendations, Revision 1***, September.

U.S. Army Corps of Engineers (USACE), 2001b, ***Requirements for the Preparation of Sampling and Analysis Plans***, Engineer Manual EM 200-1-3, February.

U.S. Army Corps of Engineers (USACE), 1987, ***Corps of Engineers Wetlands Delineation Manual***, Wetlands Research Program Technical Report T-87-1, January.

U.S. Department of Agriculture, 1961, ***Soil Survey, Calhoun County, Alabama***, Soil Conservation Service, Series 1958, No. 9, September.

U.S. Department of Commerce, National Oceanic and Atmospheric Administration (NOAA), 1998, Unedited Local Climatological Data, Anniston, Alabama, January 1998 - December 1998.

U.S. Environmental Protection Agency (EPA), 1990, ***Installation Assessment, Army Closure Program, Fort McClellan, Anniston, Alabama***, (TS-PIC-89334), Environmental Photographic Interpretation Center Report (EPIC), Environmental Monitoring Systems Laboratory.

- 1 Warman, J. C., and L. V. Causey, 1962, ***Geology and Groundwater Resources of Calhoun***
- 2 ***County, Alabama***, Alabama Geological Survey County Report 7.

ATTACHMENT 1

LIST OF ABBREVIATIONS AND ACRONYMS

List of Abbreviations and Acronyms

2-ADNT	2-amino-4,6-dinitrotoluene	AT	averaging time	CCV	continuing calibration verification
4-ADNT	4-amino-2,6-dinitrotoluene	atm-m ³ /mol	atmospheres per cubic meter per mole	CD	compact disc
2,4-D	2,4-dichlorophenoxyacetic acid	ATSDR	Agency for Toxic Substances and Disease Registry	CDTF	Chemical Defense Training Facility
2,4,5-T	2,4,5-trichlorophenoxyacetic acid	ATV	all-terrain vehicle	CEHNC	U.S. Army Engineering and Support Center, Huntsville
2,4,5-TP	2,4,5-trichlorophenoxypropionic acid	AUF	area use factor	CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
3D	3D International Environmental Group	AWARE	Associated Water and Air Resources Engineers, Inc.	CERFA	Community Environmental Response Facilitation Act
AB	ambient blank	AWQC	ambient water quality criteria	CESAS	Corps of Engineers South Atlantic Savannah
AbB3	Anniston gravelly clay loam, 2 to 6 percent slopes, severely eroded	AWWSB	Anniston Water Works and Sewer Board	CF	conversion factor
AbC3	Anniston gravelly clay loam, 6 to 10 percent slopes, severely eroded	‘B’	Analyte detected in laboratory or field blank at concentration greater than the reporting limit (and greater than zero)	CFC	chlorofluorocarbon
AbD3	Anniston and Allen gravelly clay loams, 10 to 15 percent slopes, eroded	BAF	bioaccumulation factor	CFDP	Center for Domestic Preparedness
ABLM	adult blood lead model	BBGR	Baby Bains Gap Road	CFR	Code of Federal Regulations
Abs	skin absorption	BCF	blank correction factor; bioconcentration factor	CG	phosgene (carbonyl chloride)
ABS	dermal absorption factor	BCT	BRAC Cleanup Team	CGI	combustible gas indicator
AC	hydrogen cyanide	BERA	baseline ecological risk assessment	ch	inorganic clays of high plasticity
ACAD	AutoCadd	BEHP	bis(2-ethylhexyl)phthalate	CHPPM	U.S. Army Center for Health Promotion and Preventive Medicine
AcB2	Anniston and Allen gravelly loams, 2 to 6 percent slopes, eroded	BFB	bromofluorobenzene	CIH	Certified Industrial Hygienist
AcC2	Anniston and Allen gravelly loams, 6 to 10 percent slopes, eroded	BFE	base flood elevation	CK	cyanogen chloride
AcD2	Anniston and Allen gravelly loams, 10 to 15 percent slopes, eroded	BG	Bacillus globigii	cl	inorganic clays of low to medium plasticity
AcE2	Anniston and Allen gravelly loams, 15 to 25 percent slopes, eroded	BGR	Bains Gap Road	Cl	chlorinated
ACGIH	American Conference of Governmental Industrial Hygienists	bgs	below ground surface	CLP	Contract Laboratory Program
AdE	Anniston and Allen stony loam, 10 to 25 percent slope	BHC	hexachlorocyclohexane	cm	centimeter
ADEM	Alabama Department of Environmental Management	BHHRA	baseline human health risk assessment	CN	chloroacetophenone
ADPH	Alabama Department of Public Health	BIRTC	Branch Immaterial Replacement Training Center	CNB	chloroacetophenone, benzene, and carbon tetrachloride
AEC	U.S. Army Environmental Center	bkg	background	CNS	chloroacetophenone, chloropicrin, and chloroform
AEDA	ammunition, explosives, and other dangerous articles	bls	below land surface	CO	carbon monoxide
AEL	airborne exposure limit	BOD	biological oxygen demand	CO ₂	carbon dioxide
AET	adverse effect threshold	Bp	soil-to-plant biotransfer factors	Co-60	cobalt-60
AF	soil-to-skin adherence factor	BRAC	Base Realignment and Closure	CoA	Code of Alabama
AHA	ammunition holding area	Braun	Braun Intertec Corporation	COC	chain of custody; chemical of concern
AL	Alabama	BSAF	biota-to-sediment accumulation factors	COE	Corps of Engineers
ALARNG	Alabama Army National Guard	BSC	background screening criterion	Con	skin or eye contact
ALAD	δ-aminolevulinic acid dehydratase	BTAG	Biological Technical Assistance Group	COPC	chemical of potential concern
ALDOT	Alabama Department of Transportation	BTEX	benzene, toluene, ethyl benzene, and xylenes	COPEC	constituent of potential ecological concern
amb.	amber	BTOC	below top of casing	CPOM	coarse particulate organic matter
amsl	above mean sea level	BTV	background threshold value	CPSS	chemicals present in site samples
ANAD	Anniston Army Depot	BW	biological warfare; body weight	CQCSM	Contract Quality Control System Manager
AOC	area of concern	BZ	breathing zone; 3-quinuclidinyl benzilate	CRDL	contract-required detection limit
AP	armor piercing	C	ceiling limit value	CRL	certified reporting limit
APEC	areas of potential ecological concern	Ca	carcinogen	CRQL	contract-required quantitation limit
APT	armor-piercing tracer	CaCO ₃	calcium carbonate	CRZ	contamination reduction zone
AR	analysis request	CAA	Clean Air Act	Cs-137	cesium-137
ARAR	applicable or relevant and appropriate requirement	CAB	chemical warfare agent breakdown products	CS	ortho-chlorobenzylidene-malononitrile
AREE	area requiring environmental evaluation	CACM	Chemical Agent Contaminated Media	CSEM	conceptual site exposure model
AS/SVE	air sparging/soil vapor extraction	CAMU	corrective action management unit	CSM	conceptual site model
ASP	Ammunition Supply Point	CBR	chemical, biological, and radiological	CT	central tendency
ASR	Archives Search Report	CCAL	continuing calibration	ctr.	container
AST	aboveground storage tank	CCB	continuing calibration blank	CWA	chemical warfare agent; Clean Water Act
ASTM	American Society for Testing and Materials			CWM	chemical warfare material; clear, wide mouth

List of Abbreviations and Acronyms (Continued)

CX	dichloroformoxime	EE/CA	engineering evaluation and cost analysis	FOMRA	Former Ordnance Motor Repair Area
‘D’	duplicate; dilution	Eh	oxidation-reduction potential	FOST	Finding of Suitability to Transfer
D&I	detection and identification	Elev.	elevation	Foster Wheeler	Foster Wheeler Environmental Corporation
DAAMS	depot area agent monitoring station	EM	electromagnetic	FR	Federal Register
DAF	dilution-attenuation factor	EMI	Environmental Management Inc.	Frtn	fraction
DANC	decontamination agent, non-corrosive	EM31	Geonics Limited EM31 Terrain Conductivity Meter	FS	field split; feasibility study
°C	degrees Celsius	EM61	Geonics Limited EM61 High-Resolution Metal Detector	FSP	field sampling plan
°F	degrees Fahrenheit	EOD	explosive ordnance disposal	ft	feet
DCA	dichloroethane	EODT	explosive ordnance disposal team	ft/day	feet per day
DCE	dichloroethene	EPA	U.S. Environmental Protection Agency	ft/ft	feet per foot
DDD	dichlorodiphenyldichloroethane	EPC	exposure point concentration	ft/yr	feet per year
DDE	dichlorodiphenyldichloroethene	EPIC	Environmental Photographic Interpretation Center	FTA	Fire Training Area
DDT	dichlorodiphenyltrichloroethane	EPRI	Electrical Power Research Institute	FTMC	Fort McClellan
DEH	Directorate of Engineering and Housing	EPT	Ephemeroptera, Plecoptera, Trichoptera	FTRRA	FTMC Reuse & Redevelopment Authority
DEHP	di(2-ethylhexyl)phthalate	ER	equipment rinsate	g	gram
DEP	depositional soil	ERA	ecological risk assessment	g/m ³	gram per cubic meter
DFTPP	decafluorotriphenylphosphine	ER-L	effects range-low	G-856	Geometrics, Inc. G-856 magnetometer
DI	deionized	ER-M	effects range-medium	G-858G	Geometrics, Inc. G-858G magnetic gradiometer
DID	data item description	ESE	Environmental Science and Engineering, Inc.	GAF	gastrointestinal absorption factor
DIMP	di-isopropylmethylphosphonate	ESL	ecological screening level	gal	gallon
DM	dry matter; adamsite	ESMP	Endangered Species Management Plan	gal/min	gallons per minute
DMBA	dimethylbenz(a)anthracene	ESN	Environmental Services Network, Inc.	GB	sarin (isopropyl methylphosphonofluoridate)
DMMP	dimethylmethylphosphonate	ESV	ecological screening value	gc	clay gravels; gravel-sand-clay mixtures
DNAPL	dense nonaqueous-phase liquid	ET	exposure time	GC	gas chromatograph
DNT	dinitrotoluene	EU	exposure unit	GCL	geosynthetic clay liner
DO	dissolved oxygen	Exp.	Explosives	GC/MS	gas chromatograph/mass spectrometer
DOD	U.S. Department of Defense	EXTOXNET	Extension Toxicology Network	GCR	geosynthetic clay liner
DOJ	U.S. Department of Justice	E-W	east to west	GFAA	graphite furnace atomic absorption
DOT	U.S. Department of Transportation	EZ	exclusion zone	GIS	Geographic Information System
DP	direct-push	FAR	Federal Acquisition Regulations	gm	silty gravels; gravel-sand-silt mixtures
DPDO	Defense Property Disposal Office	FB	field blank	gp	poorly graded gravels; gravel-sand mixtures
DPT	direct-push technology	FBI	Family Biotic Index	gpm	gallons per minute
DQO	data quality objective	FD	field duplicate	GPR	ground-penetrating radar
DRMO	Defense Reutilization and Marketing Office	FDC	Former Decontamination Complex	GPS	global positioning system
DRO	diesel range organics	FDA	U.S. Food and Drug Administration	GRA	general response action
DS	deep (subsurface) soil	Fe ⁺³	ferric iron	GS	ground scar
DS2	Decontamination Solution Number 2	Fe ⁺²	ferrous iron	GSA	General Services Administration; Geologic Survey of Alabama
DSERTS	Defense Site Environmental Restoration Tracking System	FedEx	Federal Express, Inc.	GSBP	Ground Scar Boiler Plant
DWEL	drinking water equivalent level	FEMA	Federal Emergency Management Agency	GSSI	Geophysical Survey Systems, Inc.
E&E	Ecology and Environment, Inc.	FFCA	Federal Facilities Compliance Act	GST	ground stain
EB	equipment blank	FFE	field flame expedient	GW	groundwater
EBS	environmental baseline survey	FFS	focused feasibility study	gw	well-graded gravels; gravel-sand mixtures
EC ₂₀	effects concentration for 20 percent of a test population	FI	fraction of exposure	H&S	health and safety
EC ₅₀	effects concentration for 50 percent of a test population	Fil	filtered	HA	hand auger
ECBC	Edgewood Chemical Biological Center	Flt	filtered	HC	mixture of hexachloroethane, aluminum powder, and zinc oxide (smoke producer)
ED	exposure duration	FMDC	Fort McClellan Development Commission	HCl	hydrochloric acid
EDD	electronic data deliverable	FML	flexible membrane liner	HD	distilled mustard (bis-[dichloroethyl]sulfide)
EF	exposure frequency	f _{oc}	fraction organic carbon		
EDQL	ecological data quality level				

List of Abbreviations and Acronyms *(Continued)*

HDPE	high-density polyethylene	JeB2	Jefferson gravelly fine sandy loam, 2 to 6 percent slopes, eroded	µg/g	micrograms per gram
HE	high explosive	JeC2	Jefferson gravelly fine sandy loam, 6 to 10 percent slopes, eroded	µg/kg	micrograms per kilogram
HEAST	Health Effects Assessment Summary Tables	JfB	Jefferson stony fine sandy loam, 0 to 10 percent slopes have strong slopes	µg/L	micrograms per liter
Herb.	herbicides	JPA	Joint Powers Authority	µmhos/cm	micromhos per centimeter
HHRA	human health risk assessment	K	conductivity	MeV	mega electron volt
HI	hazard index	K _d	soil-water distribution coefficient	min	minimum
H ₂ O ₂	hydrogen peroxide	kg	kilogram	MINICAMS	miniature continuous air monitoring system
HPLC	high-performance liquid chromatography	KeV	kilo electron volt	ml	inorganic silts and very fine sands
HNO ₃	nitric acid	K _{oc}	organic carbon partitioning coefficient	mL	milliliter
HQ	hazard quotient	K _{ow}	octonal-water partition coefficient	mm	millimeter
HQ _{screen}	screening-level hazard quotient	KMnO ₄	potassium permanganate	MM	mounded material
hr	hour	L	liter; Lewisite (dichloro-[2-chloroethyl]sulfide)	MMBtu/hr	million Btu per hour
HRC	hydrogen releasing compound	L/kg/day	liters per kilogram per day	MNA	monitored natural attenuation
HSA	hollow-stem auger	l	liter	MnO ₄ -	permanganate ion
HSDB	Hazardous Substance Data Bank	LAW	light anti-tank weapon	MOA	Memorandum of Agreement
HTRW	hazardous, toxic, and radioactive waste	lb	pound	MOGAS	motor vehicle gasoline
‘I’	out of control, data rejected due to low recovery	LBP	lead-based paint	MOUT	Military Operations in Urban Terrain
IASPOW	Impact Area South of POW Training Facility	LC	liquid chromatography	MP	Military Police
IATA	International Air Transport Authority	LCS	laboratory control sample	MPA	methyl phosphonic acid
ICAL	initial calibration	LC ₅₀	lethal concentration for 50 percent population tested	MPC	maximum permissible concentration
ICB	initial calibration blank	LD ₅₀	lethal dose for 50 percent population tested	MPM	most probable munition
ICP	inductively-coupled plasma	LEL	lower explosive limit	MQL	method quantitation limit
ICRP	International Commission on Radiological Protection	LOAEL	lowest-observed-advserse-effects-level	MR	molasses residue
ICS	interference check sample	LOEC	lowest-observable-effect-concentration	MRL	method reporting limit
ID	inside diameter	LRA	land redevelopment authority	MS	matrix spike
IDL	instrument detection limit	LT	less than the certified reporting limit	mS/cm	millisiemens per centimeter
IDLH	immediately dangerous to life or health	LUC	land-use control	mS/m	millisiemens per meter
IDM	investigative-derived media	LUCAP	land-use control assurance plan	MSD	matrix spike duplicate
IDW	investigation-derived waste	LUCIP	land-use control implementation plan	MTBE	methyl tertiary butyl ether
IEUBK	Integrated Exposure Uptake Biokinetic	max	maximum	msl	mean sea level
IF	ingestion factor; inhalation factor	MB	method blank	MtD3	Montevallo shaly, silty clay loam, 10 to 40 percent slopes , severely eroded
ILCR	incremental lifetime cancer risk	MCL	maximum contaminant level	mV	millivolts
IMPA	isopropylmethyl phosphonic acid	MCLG	maximum contaminant level goal	MW	monitoring well
IMR	Iron Mountain Road	MCPA	4-chloro-2-methylphenoxyacetic acid	MWI&MP	Monitoring Well Installation and Management Plan
in.	inch	MCPP	2-(2-methyl-4-chlorophenoxy)propionic acid	Na	sodium
Ing	ingestion	MCS	media cleanup standard	NA	not applicable; not available
Inh	inhalation	MD	matrix duplicate	NAD	North American Datum
IP	ionization potential	MDC	maximum detected concentration	NAD83	North American Datum of 1983
IPS	International Pipe Standard	MDCC	maximum detected constituent concentration	NaMnO ₄	sodium permanganate
IR	ingestion rate	MDL	method detection limit	NAVD88	North American Vertical Datum of 1988
IRDMIS	Installation Restoration Data Management Information System	mg	milligrams	NAS	National Academy of Sciences
IRIS	Integrated Risk Information Service	mg/kg	milligrams per kilogram	NCEA	National Center for Environmental Assessment
IRP	Installation Restoration Program	mg/kg/day	milligram per kilogram per day	NCP	National Contingency Plan
IS	internal standard	mg/kgbw/day	milligrams per kilogram of body weight per day	NCRP	National Council on Radiation Protection and Measurements
ISCP	Installation Spill Contingency Plan	mg/L	milligrams per liter	ND	not detected
IT	IT Corporation	mg/m ³	milligrams per cubic meter	NE	no evidence; northeast
ITEMS	IT Environmental Management System™	mh	inorganic silts, micaceous or diatomaceous fine, sandy or silt soils	ne	not evaluated
‘J’	estimated concentration	MHz	megahertz	NEW	net explosive weight

List of Abbreviations and Acronyms (Continued)

NFA	No Further Action
NG	National Guard
NGP	National Guardsperson
ng/L	nanograms per liter
NGVD	National Geodetic Vertical Datum
Ni	nickel
NIC	notice of intended change
NIOSH	National Institute for Occupational Safety and Health
NIST	National Institute of Standards and Technology
NLM	National Library of Medicine
NO ₃ ⁻	nitrate
NOEC	no-observable-effect-concentration
NPDES	National Pollutant Discharge Elimination System
NPW	net present worth
No.	number
NOAA	National Oceanic and Atmospheric Administration
NOAEL	no-observed-adverse-effects-level
NR	not requested; not recorded; no risk
NRC	National Research Council
NRCC	National Research Council of Canada
NRHP	National Register of Historic Places
NRT	near real time
ns	nanosecond
N-S	north to south
NS	not surveyed
NSA	New South Associates, Inc.
nT	nanotesla
nT/m	nanoteslas per meter
NTU	nephelometric turbidity unit
nv	not validated
O ₂	oxygen
O ₃	ozone
O&G	oil and grease
O&M	operation and maintenance
OB/OD	open burning/open detonation
OD	outside diameter
OE	ordnance and explosives
oh	organic clays of medium to high plasticity
OH•	hydroxyl radical
ol	organic silts and organic silty clays of low plasticity
OP	organophosphorus
ORC	Oxygen Releasing Compound
ORP	oxidation-reduction potential
OSHA	Occupational Safety and Health Administration
OSWER	Office of Solid Waste and Emergency Response
OVM-PID/FID	organic vapor meter-photoionization detector/flame ionization detector
OWS	oil/water separator
oz	ounce

PA	preliminary assessment
PAH	polynuclear aromatic hydrocarbon
PARCCS	precision, accuracy, representativeness, comparability, completeness, and sensitivity
Parsons	Parsons Engineering Science, Inc.
Pb	lead
PBMS	performance-based measurement system
PC	permeability coefficient
PCB	polychlorinated biphenyl
PCDD	polychlorinated dibenzo-p-dioxins
PCDF	polychlorinated dibenzofurans
PCE	perchloroethene
PCP	pentachlorophenol
PDS	Personnel Decontamination Station
PEF	particulate emission factor
PEL	permissible exposure limit
PERA	preliminary ecological risk assessment
PERC	perchloroethene
PES	potential explosive site
Pest.	pesticides
PETN	pentaerythritoltetranitrate
PFT	portable flamethrower
PG	professional geologist
PID	photoionization detector
PkA	Philo and Stendal soils local alluvium, 0 to 2 percent slopes
PM	project manager
POC	point of contact
POL	petroleum, oils, and lubricants
POTW	publicly owned treatment works
POW	prisoner of war
PP	peristaltic pump; Proposed Plan
ppb	parts per billion
ppbv	parts per billion by volume
PPE	personal protective equipment
ppm	parts per million
PPMP	Print Plant Motor Pool
ppt	parts per thousand
PR	potential risk
PRA	preliminary risk assessment
PRG	preliminary remediation goal
PS	chloropicrin
PSSC	potential site-specific chemical
pt	peat or other highly organic silts
PVC	polyvinyl chloride
QA	quality assurance
QA/QC	quality assurance/quality control
QAM	quality assurance manual
QAO	quality assurance officer

QAP	installation-wide quality assurance plan
QC	quality control
QST	QST Environmental, Inc.
qty	quantity
Qual	qualifier
R	rejected data; resample; retardation factor
R&A	relevant and appropriate
RA	remedial action
RAO	remedial action objective
RBC	risk-based concentration; red blood cell
RBRG	risk-based remedial goal
RCRA	Resource Conservation and Recovery Act
RCWM	Recovered Chemical Warfare Material
RD	remedial design
RDX	cyclotrimethylenetrinitramine
ReB3	Rarden silty clay loams
REG	regular field sample
REL	recommended exposure limit
RFA	request for analysis
RfC	reference concentration
RfD	reference dose
RGO	remedial goal option
RI	remedial investigation
RL	reporting limit
RME	reasonable maximum exposure
ROD	Record of Decision
RPD	relative percent difference
RR	range residue
RRF	relative response factor
RRSE	Relative Risk Site Evaluation
RSD	relative standard deviation
RTC	Recruiting Training Center
RTECS	Registry of Toxic Effects of Chemical Substances
RTK	real-time kinematic
RWIMR	Ranges West of Iron Mountain Road
SA	exposed skin surface area
SAD	South Atlantic Division
SAE	Society of Automotive Engineers
SAIC	Science Applications International Corporation
SAP	installation-wide sampling and analysis plan
SARA	Superfund Amendments and Reauthorization Act
sc	clayey sands; sand-clay mixtures
Sch.	schedule
SCM	site conceptual model
SD	sediment
SDG	sample delivery group
SDWA	Safe Drinking Water Act
SDZ	safe distance zone; surface danger zone

List of Abbreviations and Acronyms (Continued)

SEMS	Southern Environmental Management & Specialties, Inc.	SWMU	solid waste management unit	USATEU	U.S. Army Technical Escort Unit
SF	cancer slope factor	SWPP	storm water pollution prevention plan	USATHAMA	U.S. Army Toxic and Hazardous Material Agency
SFSP	site-specific field sampling plan	SZ	support zone	USC	United States Code
SGF	standard grade fuels	TAL	target analyte list	USCS	Unified Soil Classification System
Shaw	Shaw Environmental, Inc.	TAT	turn around time	USDA	U.S. Department of Agriculture
SHP	installation-wide safety and health plan	TB	trip blank	USEPA	U.S. Environmental Protection Agency
SI	site investigation	TBC	to be considered	USFWS	U.S. Fish and Wildlife Service
SINA	Special Interest Natural Area	TCA	trichloroethane	USGS	U.S. Geological Survey
SL	standing liquid	TCDD	2,3,7,8-tetrachlorodibenzo-p-dioxin	UST	underground storage tank
SLERA	screening-level ecological risk assessment	TCDF	tetrachlorodibenzofurans	UTL	upper tolerance level; upper tolerance limit
sm	silty sands; sand-silt mixtures	TCE	trichloroethene	UXO	unexploded ordnance
SM	Serratia marcescens	TCL	target compound list	UXOQCS	UXO Quality Control Supervisor
SMDP	Scientific Management Decision Point	TCLP	toxicity characteristic leaching procedure	UXOSO	UXO safety officer
s/n	signal-to-noise ratio	TDEC	Tennessee Department of Environment and Conservation	V	vanadium
SO ₄ ⁻²	sulfate	TDGCL	thiodiglycol	VC	vinyl chloride
SOD	soil oxidant demand	TDGCLA	thiodiglycol chloroacetic acid	VOA	volatile organic analyte
SOP	standard operating procedure	TEA	triethylaluminum	VOC	volatile organic compound
SOPQAM	U.S. EPA's <i>Standard Operating Procedure/Quality Assurance Manual</i>	Tetryl	trinitrophenylmethylnitramine	VOH	volatile organic hydrocarbon
sp	poorly graded sands; gravelly sands	TERC	Total Environmental Restoration Contract	VQlfr	validation qualifier
SP	submersible pump	THI	target hazard index	VQual	validation qualifier
SPCC	system performance calibration compound	TIC	tentatively identified compound	VX	nerve agent (O-ethyl-S-[diisopropylaminoethyl]-methylphosphonothiolate)
SPCS	State Plane Coordinate System	TLV	threshold limit value	WAC	Women's Army Corps
SPM	sample planning module	TN	Tennessee	Weston	Roy F. Weston, Inc.
SQRT	screening quick reference tables	TNB	trinitrobenzene	WP	installation-wide work plan
Sr-90	strontium-90	TNT	trinitrotoluene	WRS	Wilcoxon rank sum
SRA	streamlined human health risk assessment	TOC	top of casing; total organic carbon	WS	watershed
SRI	supplemental remedial investigation	TPH	total petroleum hydrocarbons	WSA	Watershed Screening Assessment
SRM	standard reference material	TR	target cancer risk	WWI	World War I
Ss	stony rough land, sandstone series	TRADOC	U.S. Army Training and Doctrine Command	WWII	World War II
SS	surface soil	TRPH	total recoverable petroleum hydrocarbons	XRF	x-ray fluorescence
SSC	site-specific chemical	TRV	toxicity reference value	yd ³	cubic yards
SSHO	site safety and health officer	TSCA	Toxic Substances Control Act		
SSHP	site-specific safety and health plan	TSDF	treatment, storage, and disposal facility		
SSL	soil screening level	TSS	total suspended solids		
SSSL	site-specific screening level	TWA	time-weighted average		
SSSSL	site-specific soil screening level	UCL	upper confidence limit		
STB	supertropical bleach	UCR	upper certified range		
STC	source-term concentration	‘U’	not detected above reporting limit		
STD	standard deviation	UIC	underground injection control		
STEL	short-term exposure limit	UF	uncertainty factor		
STL	Severn-Trent Laboratories	URF	unit risk factor		
STOLS	Surface Towed Ordnance Locator System®	USACE	U.S. Army Corps of Engineers		
Std. units	standard units	USACHPPM	U.S. Army Center for Health Promotion and Preventive Medicine		
SU	standard unit	USAEC	U.S. Army Environmental Center		
SUXOS	senior UXO supervisor	USAEHA	U.S. Army Environmental Hygiene Agency		
SVOC	semivolatile organic compound	USACMLS	U.S. Army Chemical School		
SW	surface water	USAMPS	U.S. Army Military Police School		
SW-846	U.S. EPA's <i>Test Methods for Evaluating Solid Waste: Physical/Chemical Methods</i>	USATCES	U.S. Army Technical Center for Explosive Safety		